86-43333

Chlorinated Organic Compounds in Ground Water at Roosevelt Field, Nassau County, Long Island, New York

U.S. GEOLOGICAL SURVEY
Water-Resources Investigations
Report 86-4333

Prepared in cooperation with the
NASSAU COUNTY DEPARTMENT
OF PUBLIC WORKS

I 19.42/4:

READEX FICHE best copy available

CHLORINATED ORGANIC COMPOUNDS IN GROUND WATER AT ROOSEVELT FIELD, NASSAU COUNTY, LONG ISLAND, NEW YORK

by David A. V. Eckhardt and Kenneth A. Pearsall

U.S. GEOLOGICAL SURVEY

Water-Resources Investigations
Report 86-4333

Prepared in cooperation with the

NASSAU COUNTY DEPARTMENT OF PUBLIC WORKS

Syosset, New York

1989

DEPARTMENT OF THE INTERIOR

DONALD PAUL HODEL, Secretary

U.S. GEOLOGICAL SURVEY

Dallas L. Peck, Director

For further information call:

U.S. Geological Survey
Water Resources Division
5 Aerial Way
Syosset, New York 11791

Copies of this report may be obtained from:

U.S. Geological Survey
Books and Open-File Reports Section
Federal Center, Bldg. 41
Box 25425
Denver, CO 80225

CONTENTS

	Page
Abstract	1
Introduction	1
Purpose and scope	3
Location and description of the Roosevelt Field area	4
Methods of study	4
Well network and sampling procedures	5
Chemical analyses	8
Quality assurance	9
Accuracy of measurements	9
Acknowledgments	9
Hydrogeologic setting	10
Magothy aquifer	11
Upper glacial aquifer	11
Hydrologic environment	11
Precipitation	11
Water use	12
Recharge	15
Recharge basins	15
Drain field	15
Diffusion wells	16
Ground-water movement	16
Upper glacial aquifer	16
August 1982 water table	17
August 1983 water table	20
August 1984 water table	20
Magothy aquifer	21
Downward movement of water in the aquifer system	21
Inorganic chemical constituents in ground water	23
Ground-water temperature	25
Volatile organic compounds in ground water	25
Chemical character	25
Concentrations at Roosevelt Field	26
Trichloroethylene (TCE), 1,2-dichloroethylene, and tetrachloroethylene in discharged cooling water	26
Discharge to Pembrook recharge basin	27
Discharge to Garden City Plaza drain field	27
TCE in the upper glacial aquifer	29
Original plume	29
Plume at Garden City Plaza drain field	29
Plume at Pembrook recharge basin	30
Extent of TCE contamination	31
TCE in the Magothy aquifer	33
Movement of TCE	35
Advection	36
Upper glacial aquifer	36
Magothy aquifer	36
Density-induced movement	37
Biodegradation	37
Adsorption	38
Summary and conclusions	39
References cited	42

ILLUSTRATIONS

			Page
Figure	1.	Map of Nassau County showing location of Roosevelt Field. .	2
	2.	Photographs showing Roosevelt Field area: A. December 1951. B. December 1974	6
	3.	Idealized north-south geologic section through Nassau County.	10
	4.	Bar graph showing monthly precipitation at Mineola, N.Y., during 1982-84 water years.	12
	5.	Map showing location of pumping centers and areas of cooling-water discharge at Roosevelt Field in 1983.	14
	6.	Bar graph showing total monthly pumpage from four public-supply wells at Roosevelt Field during 1983 water year. . .	14
	7.	Maps showing water-table configuration at Roosevelt Field: A. August 1982. B. August 1983. C. August 1984	17-19
	8.	Hydrograph showing water-table altitudes at wells N9955 near Pembrook recharge basin and N9958 near Garden City Plaza from August 1982 through January 1983	20
	9.	Hydrographs showing water-level fluctuations at wells N9955 and N10020 near southwest corner of shopping center in fall 1982 and winter 1983.	22
	10.	Maps showing trichloroethylene concentrations in the upper glacial aquifer at Roosevelt Field: A. August-September 1983. B. April-May 1984	32-33
	11.	Map showing trichloroethylene concentrations in the Magothy aquifer at Roosevelt Field, April-May 1984, before start of seasonal cooling-water pumping	34

TABLES

Table	1.	List of volatile organic compounds analyzed for in ground-water samples from Roosevelt Field, 1983-84	8
	2.	Annual pumpage from 11 public-supply wells in the Roosevelt Field area.	14
	3.	Summary of inorganic chemical analyses of ground water from wells in the Roosevelt Field area of Nassau County, 1984. . .	24

TABLES (Continued)

Page

Table 4. Concentration and discharge of volatile organic compounds in water from six cooling-water wells at Roosevelt Field, August 1984 28

5. Total organic carbon in core samples from well N10042 at Mitchel Field in central Nassau County, New York. 38

6. Data on wells in the Roosevelt Field area, Nassau County, New York. 47

7. Concentrations of volatile organic compounds in ground-water samples collected by Nassau County before 1983. 51

8. Concentrations of volatile organic compounds in ground-water samples collected by U.S. Geological Survey in 1983-84. . . . 58

PLATES

(in pocket)

Plate 1. Map showing 1983 water-table altitude in April 1984 and locations of wells in the Roosevelt Field area

2. Geologic sections A-A', B-B', C-C', D-D', and E-E' showing 1984 trichloroethylene concentrations in the Roosevelt Field area

CONVERSION FACTORS AND ABBREVIATIONS

For the convenience of readers who prefer metric (International System) units rather than the inch-pound units used in this report, the following conversion factors may be used:

Multiply inch-pound unit	by	To obtain metric unit
inch (in)	25.40	millimeter (mm)
foot (ft)	0.3048	meter (m)
mile (mi)	1.609	kilometer (km)
square mile (mi^2)	2.59	square kilometer (km^2)
foot per day (ft/d)	0.3048	meter per day (m/d)
gallon per minute (gal/min)	0.06308	liter per second (L/s)
million gallons per day (Mgal/d)	0.04381	cubic meter per second (m^3/s)
degree Fahrenheit ($^\circ F$)	$^\circ C = 5/9\ (^\circ F-32)$	degree Celsius ($^\circ C$)
foot per day (ft/d)	0.3048	meter per day (m/d)
pounds per day (lb/d)	0.4536	kilogram per day (kg/d)

Sea level: In this report "sea level" refers to the National Geodetic Vertical Datum of 1929 (NGVD of 1929)--a geodetic datum derived from a general adjustment of the first-order level nets of both the United States and Canada, formerly called "sea level datum of 1929."

CHLORINATED ORGANIC COMPOUNDS IN GROUND WATER AT ROOSEVELT FIELD, NASSAU COUNTY, LONG ISLAND, NEW YORK

by David A. V. Eckhardt and Kenneth A. Pearsall

Abstract

Trichloroethylene, 1,2-dichloroethylene, and tetrachloroethylene have been detected in ground water at Roosevelt Field near Garden City, N.Y. The 200-acre area was once an air field but is now a large shopping mall and office-building complex. One well screened 300 ft below land surface in the Magothy aquifer (Upper Cretaceous) has yielded water that contains 38,000 micrograms per liter of trichloroethylene, the principal contaminant. The source(s) of contamination have not been identified.

During 1982-84, four public-supply wells at Roosevelt Field pumped more than 4 million gallons per day for peak water demand in the summer, and seven wells pumped an additional 4 million gallons per day for warm-weather cooling. Four of the cooling-water wells pumped water from trichloroethylene-contaminated zones in the Magothy aquifer. The cooling water was discharged after use to the water-table (upper glacial) aquifer through a recharge basin and a subsurface drain field.

Three plumes of contaminated ground water have been delineated. The initial plume probably originated before the shopping center was developed and extends through both the upper glacial and Magothy aquifers; the other two plumes are in the upper glacial aquifer and originate at the two cooling-water-discharge sites. The contaminated discharge water moves radially away from both discharge sites, and the two secondary plumes have merged in the southwestern part of Roosevelt Field. In 1986, the plumes extended at least 1,000 feet south-southwest beyond Roosevelt Field along the regional ground-water flow path. Concentrations of inorganic constituents in the plumes are indistinguishable from those in the ambient ground water.

Ground-water velocity in the Magothy aquifer varies locally because the aquifer is anisotropic and heterogeneous, and because large-scale pumping increases the hydraulic gradients locally. Where clay layers are absent and sandy zones provide good vertical hydraulic connection between upper and lower parts of the aquifer system, pumping of wells screened in the middle and basal sections of the Magothy aquifer has increased the rates of downward movement of contaminants. As a result, trichloroethylene has been detected in the basal section of the Magothy aquifer, 500 feet below land surface.

INTRODUCTION

Chlorinated organic chemicals in ground water were first discovered in Nassau County in October 1975, when vinyl chloride, trichloroethylene (TCE), and tetrachloroethylene were detected in two industrial-supply wells at Bethpage (fig. 1) (Myott, 1980). A program to sample all public-supply wells



Base from U.S. Geological Survey
State base map, 1974

Figure 1.--Location of Roosevelt Field, Nassau County.

in Nassau County was begun in November 1976 after similar organic compounds were detected in five public-supply wells in the Bethpage area. Surveys of industrial and commercial establishments were conducted to identify potential sources of organic chemical contamination, such as industrial and commercial sites and chemical-waste-disposal areas (Mackay and others, 1979, p. 1). Organic compounds were commonly detected in the ground-water system in these initial surveys; the higher concentrations were mainly in industrialized areas and in shallow wells.

In 1982, the U.S. Geological Survey began a cooperative study with the Nassau County Department of Public Works to evaluate the occurrence and movement of VOC's[1] in ground water at Roosevelt Field--an area in the northern part of the Town of Hempstead (fig. 1) where one public-supply well and five cooling-water-supply wells have yielded water that contained TCE in excess of recommended New York State Health Department drinking-water guidelines (50 µg/L). (The public-supply well and two cooling-water wells have been subsequently abandoned.) No sources of the contamination had been identified, and a lack of adequate hydrologic information and inconsistencies in the water-quality data from this area were hindering analysis of the movement and fate of the compounds and their effects on the area's water resources. The investigation was conducted from March 1982 through September 1984.

Purpose and Scope

This report describes the results of the study, the major objective of which was to delineate the horizontal and vertical distribution and temporal trends of VOC concentrations in the aquifer system at Roosevelt Field. A second objective was to evaluate hydrologic factors that determine the distribution and movement of organic compounds in the ground-water system. Factors considered were natural recharge from precipitation, effects of seasonal ground-water pumping for cooling water and public supply, discharge of used cooling water during summer and early fall to the upper glacial aquifer, hydraulic characteristics and dimensions of the aquifer system, and regional ground-water flow patterns.

Most of the work concerned evaluation of factors that affected the movement of ground water and associated advective movement of dissolved organic chemical compounds. Other factors such as dispersion, biochemical degradation, or volatilization were not studied in detail but are discussed briefly. Most of the sampling was done within Roosevelt Field, but ground-water levels were measured and samples collected from the 10-mi^2 area surrounding Roosevelt Field (fig. 1 and pl. 1) as well.

This report describes the distribution of chlorinated compounds, primarily TCE, in the ground-water system at Roosevelt Field and discusses factors that affect contaminant movement. Concentrations of TCE, 1,2-dichloroethylene (DCE), and tetrachloroethylene (PCE) in samples from wells in the Roosevelt Field area are reported in tables 7 and 8 (at end of report); table 7 contains data collected by Nassau County before 1983, and table 8 contains data collected in 1983-84 by the Geological Survey. The data in

[1] In this report, chlorinated organic compounds are referred to as VOC's (volatile organic compounds).

table 7 were used to delineate plumes of TCE in the upper glacial aquifer and the Magothy aquifer on two maps. Water-table maps that represent four periods are given--August 1982, August 1983, April 1984, and August 1984; the regional movement of ground water is also described. Five geologic sections (pl. 2) show the dimensions and lithology of the aquifer system in the Roosevelt Field area and concentrations of TCE at various depths. An analysis of the effects of seasonal pumping of TCE-contaminated ground water and its discharge after use to the shallow aquifer at two locations also is presented.

Location and Description of the Roosevelt Field Area

The area addressed in this report encompasses about 20 mi^2 in central Nassau County and lies on the boundary between the Towns of Hempstead and North Hempstead (fig. 1, pl. 1). Roosevelt Field was a commercial airfield from about 1924 to 1951 (fig. 2A). (Charles Lindbergh departed from this field on his historic trans-Atlantic flight in 1927). The field is now the site of a large shopping mall and office-building complex and is surrounded by residential and commercial areas and light industry (fig. 2B).

Directly southeast of Roosevelt Field is the site of Mitchel Field, a U.S. Air Force base until 1957 and currently occupied by Nassau County Community College, Hofstra University, Nassau Veterans Memorial Coliseum, and several other county and commercial facilities (pl. 1). Nassau County is currently developing Mitchel Field and neighboring Eisenhower Park as a water-supply area. VOC's were detected at the northeast corner of the Mitchel Field site during exploratory well drilling by Nassau County in 1978. In one well (N9765, near Mitchel Field, pl. 1), ground water contained total VOC concentrations exceeding 260,000 µg/L. The source has been determined to be from a former industrial-solvent-distributor and a State mandated soil and ground-water remedial program has been in-place since 1985. Work by the USEPA has also begun on another former industrial-solvent distributor site directly to the west. The contamination at Mitchel Field is currently under study by Nassau County and others, and, for that reason, the area shaded on plate 1 was excluded from this study.

Methods of Study

Ground water was sampled by the Geological Survey during late summer 1983 and spring 1984 to (1) delineate the area affected by VOC's; (2) determine the distribution of VOC's in the aquifer system, (3) examine the effect of ground-water pumping and discharge of contaminated cooling water on the movement of contaminants in the area, and (4) provide a measure of background concentrations of VOC's in areas bordering Roosevelt Field. The first set of samples was collected during August and September 1983 at the end of the summer pumping season and included samples from 62 wells in the immediate vicinity of the observed contamination. The second set was collected from April through June 1984, at the beginning of the summer pumping season. The second phase included sampling to provide background water-quality data and entailed a more intensive effort to sample all wells in the Roosevelt Field area, including most public-supply wells and monitoring wells.

In addition to the primary sampling phases in August 1983 and April 1984, a set of samples was collected in August 1984 from cooling-water wells that

contributed contaminated water to Pembrook recharge basin and Garden City Plaza drain field. The discharge water from the wells at both locations was sampled concurrently, as was ground water near each discharge point. Additional ground-water samples were collected as necessary near the cooling-water-discharge areas to define seasonal changes in ground-water quality. In all, 224 water samples were collected from 52 monitoring wells, 28 public-supply wells, and 25 cooling-water wells.

Well Network and Sampling Procedures

A well network consisting of 52 monitoring wells, 28 public-supply wells, and 25 cooling-water supply wells was established within the 10-mi^2 Roosevelt Field area for collection of hydrogeologic and water-quality data. Most monitoring wells were installed before the study began and therefore represent a variety of casing sizes, construction materials, and installation methods. The monitoring wells typically have either 2- or 4-in steel casings and stainless steel screens. To supplement the well network, seven additional wells were drilled by augering in the upper glacial aquifer, and two more were drilled to the Magothy aquifer by the mud rotary method. Information on wells in the network is given in table 6 (at end of report), and well locations are shown on plate 1.

The procedures used for monitoring-well sampling depended on the casing diameter and well depth. Most wells screened in the upper glacial aquifer were sampled with a Johnson-Keck[1] 1.75-in-diameter positive-displacement screw-type submersible pump. The pump is made of stainless steel with an ethylene propylene rubber (EPDM) stator; Teflon[1] tubing was used to transmit the pumped water to land surface. The usual procedure was to place the pump intake just above the well screen and pump at least 3 casing volumes (about 1 hour) before collecting samples. Pump placement, flow rate, and pumping duration were duplicated when wells were resampled. Tests of this sampling procedure have indicated that it provides representative samples of ground water at VOC concentrations between 1 and 1,000 µg/L (Pearsall and Eckhardt, 1987). The pump was flushed after each sampling with 2 to 5 gal of clean tap water. Samples of flush water were collected after sampling and analyzed by purge-and-trap liquid-sample concentration and gas chromatography with flame-ionization detection (PT-GC/FID) scans for volatile compounds to verify the cleanliness of the sampling equipment. Permanent pump installations were used to collect samples for water-quality analyses at public-supply and cooling-water wells.

Field data recorded during pumping included initial water level, pump-intake depth, pumping time, flow rate, and drawdown. Specific conductance, pH, and temperature of all samples were measured during sampling; dissolved oxygen concentrations (DO) were measured in selected samples.

Four-inch-diameter wells deeper than 100 ft were evacuated and sampled with a 4-inch-diameter Goulds 1-hp submersible pump. Water was transmitted to the surface through 1.25-inch (outside diameter) Teflon pipe and sampled at the well head. The procedures used and precautions taken were similar to

---

[1] Use of the brand name in this report is for identification purposes only and does not constitute endorsement by the U.S. Geological Survey.

LONG ISLAND RAILROAD
OLD COUNTRY ROAD
ROOSEVELT AIR FIELD
Aircraft Maintenance
Hangers
CLINTON ROAD
0 250 500 FEET
0 50 100 150 METERS
Approx scale

Figure 2.--Roosevelt Field area. Above, December 1951. Below, December 1974. (Photographs courtesy of Skyview Survey, Inc., Westbury, N.Y.)

those used with the 1.75-inch submersible pump. Wells with a casing diameter of less than 2 inches were sampled with bottom-entry Teflon bailers. Sampling equipment and techniques are described and evaluated by Pearsall and Eckhardt (1987). Production wells with permanently installed pumps such as public-supply wells or cooling-water wells were sampled at a tap or faucet as near the well head as possible after the pump had been running at least 1 hour.

Sample containers were prepared and supplied by the analyzing laboratory. Samples for VOC analysis were collected in glass bottles and sealed with Teflon-lined caps or septa. These sample containers were filled with minimum aeration of the sample; this was usually done by routing sample water from the pump outlet into the sample container through a Teflon tube whose exit end was below the water surface in the sample container. All samples for inorganic-constituent analysis were collected in containers supplied with preservatives added by the analyzing laboratory. Samples for dissolved inorganic constituents were filtered through a 0.45-μm cellulose-membrane filter. Samples for metals analysis were preserved with nitric acid. All samples were stored in a cooler with ice for preservation after collection.

Chemical Analyses

The VOC's analyzed for in this investigation are listed in table 1. Trichloroethylene, *cis*-1,2-dichloroethylene, and tetrachloroethylene were the principal compounds detected in most water samples. Concentrations of these constituents before and during this study are given at the end of this report in tables 7 and 8, respectively. Total VOC's (the sum of concentrations for all compounds listed in table 1) are included. A summary of the concentrations of inorganic chemical constituent and physical-property values are listed in table 3 (p. 24). Samples were analysed by the Nassau County Department of Health, Division of Laboratories and Research, in Hempstead, N.Y., by procedures described in Narang and Bush (1980) and the U.S. Environmental Protection Agency (1979a).

Table 1.--List of volatile organic compounds analyzed for in ground-water samples from Roosevelt Field, 1983-84.

Volatile Halogenated Compounds	
Trichlorofluoromethane	Tetrachloroethylene
Methylene chloride	Bromoform
1,1,2-Trichlorotrifluoroethane	1,2-Dichloroethane
1,1-Dichloroethylene	1,2-Dichloropropane
cis-1,2-Dichloroethylene	*trans*-1,3-Dichloropropene
trans-1,2-Dichloroethylene	1,1,2,2-Tetrachloroethane
1,1-Dichloroethane	
Chloroform	
1,1,1-Trichloroethane	Volatile Aromatic Compounds
Carbon tetrachloride	
Trichloroethylene	Benzene
Bromodichloromethane	Toluene
cis-1,3-Dichloropropene	Chlorobenzene
Dibromochloromethane	Ethylbenzene
1,1,2-Trichloroethane	Xylene
1,2-Dibromomethane	Dichlorobenzene

Quality Assurance

All samples to be analyzed for VOC's were collected in duplicate and screened by PT-GC/FID[1] scans at the U.S. Geological Survey's Long Island office for comparision with the reporting laboratory's results. Flush blanks of rinse water from the 2-inch submersible pump were also screened to verify the cleanliness of the sampling equipment between samples. Ten percent of the VOC samples were collected in triplicate, one of which was analysed by the U.S. Geological Survey National Water-Quality Laboratory (NWQL) in Atlanta, Ga., by procedures described by Wershaw and others (1982). Surrogate spiking compounds were added to these samples by NWQL analysts before analysis to evaluate recovery efficiencies. Ten percent of samples for inorganic analysis were collected in duplicate and analyzed by the NWQL by the procedures described by Skougstad and others (1979). Both the Nassau County Department of Health Laboratory and the U.S. Geological Survey National Water Quality Laboratory participate in the Standard Reference Water Sample Program, a quality-assurance program administered by the U.S. Geological Survey.

Accuracy of Measurements

A degree of error is inherent in any measurement, and an understanding of the possible magnitude of the error is necessary to correctly interpret that measurement. Several possible sources of error are inherent in the process of ground-water sampling and analysis.

A primary source of analytical error arises from variable recovery efficiencies of very low concentrations of organic constituents from aqueous solutions. Acceptable recovery efficiencies for extraction of surrogate spiking compounds from water samples can range from 70 to 130 percent (Wershaw and others, 1982).

In addition to the inherent potential for error in analytical techniques, the quality of data depends on the ability of the field procedures to provide a sample that is truly representative of the aquifer water. The uncertainty in obtaining representative samples and in preserving them may add a degree of error, even before the sample enters the laboratory. Thus, despite rigid quality-control procedures, specific concentrations reported as representative of aquifer water at a site must be interpreted with caution.

Acknowledgments

This work was done by the U.S. Geological Survey as part of a cooperative study with Nassau County. J. F. Mulligan, P. J. Witkowski, and R. E. Denton of the Nassau County Department of Public Works helped in locating and drilling wells, coordinating vertical elevation surveys, and furnishing water levels and geophysical data. M. J. Alarcon, D. H. Myott, and J. J. Kardos of the Nassau County Health Department (NCHD), Bureau of Public Water Supply, assisted by implementing a project with the New York State Health Department

[1] Purge and trap liquid-sample concentration followed by gas chromatography with flame-ionization detection.

that provided for the drilling of 18 observation wells and sampling of public-supply wells. James Adamski, Andrew Lichtman, and Robert Porter, NCHD, Division of Laboratories and Research, coordinated the analytical laboratory services. Many private well owners and officials from water-supply departments for the Town of Hempstead, the villages of Garden City, Mineola, and Hempstead, and the water districts of Carle Place and Westbury provided access to their wells and records. B. J. Schneider of the U.S. Geological Survey did the preliminary data collection at Roosevelt Field.

HYDROGEOLOGIC SETTING

The Long Island aquifer system lies within the embayed section of the Atlantic Coastal Plain province. The island is underlain by unconsolidated Pleistocene and Cretaceous deposits of gravel, sand, silt, and clay that overlie gently dipping metamorphic and igneous Precambrian bedrock (fig. 3). The hydrogeology of Nassau County is discussed in detail by McClymonds and Franke (1972), Isbister (1966), Perlmutter and Geraghty (1963), Swarzenski (1963), Kilburn (1979), and Kilburn and Krulikas (1987).

The aquifer system in the study area consists, from oldest to youngest, of the Lloyd aquifer, which is the lower member of the Raritan Formation of Cretaceous age and rests on bedrock; the Upper Cretaceous Magothy aquifer, which is the principal aquifer for water supply in this area; and the Pleistocene upper glacial aquifer, which contains the water table. The



Figure 9.--Idealized north-south geologic section through Nassau County. (Modified from McClymonds and Franke, 1972.)

Raritan confining unit, the upper member of the Raritan Formation, consists mostly of clay and sandy clay and separates the Lloyd aquifer from the Magothy aquifer. South of the Roosevelt Field area, the Gardiners Clay (Pleistocene age) and other confining units separate the Magothy and upper glacial aquifers, but these units do not extend into the study area. Thus, the upper glacial aquifer at Roosevelt Field is in direct hydraulic contact with the Magothy aquifer. The upper zones of the aquifer system in the Roosevelt Field area are depicted in five geologic sections in plate 2; the sections were compiled from deep-well logs. This study concerned only the aquifer system above the Raritan confining unit (fig. 3) because no hydrologic or water-quality data from below the confining unit in this area were available.

Magothy Aquifer

The Magothy aquifer unconformably overlies the Raritan confining unit and consists of alternating sequences and gradations of sand, clayey sand, sandy clay, clay, lignite, and some gravel in the basal section. The deposits are fluvial deltaic and have considerable lateral and vertical heterogeneity. Although the Magothy aquifer is about 500 ft thick in the Roosevelt Field area, most of the public-supply water is taken from sand and gravel zones in the lower 150 ft. Discontinuous layers of gray lignitic clay are common in the upper zones, and the larger ones form local confining layers.

Hydraulic conductivity averages between 50 and 60 ft/d in southern Nassau County but may be as much as 190 ft/d in the basal section of the Magothy aquifer, which contains more gravel than the upper sections (McClymonds and Franke, 1972).

Upper Glacial Aquifer

The upper glacial (water-table) aquifer unconformably overlies the Magothy aquifer and consists of glacial outwash that is predominantly sand and gravel. The outwash deposits in the Roosevelt Field area are fairly uniform in particle-size distribution and lithology. Depth to water ranges from 25 to 50 ft below land surface, and the saturated thickness of the aquifer ranges from 20 to 40 ft. Hydraulic conductivity of the upper glacial aquifer in southern Nassau County averages about 250 ft/d (McClymonds and Franke, 1972).

HYDROLOGIC ENVIRONMENT

Precipitation

Precipitation is the only natural source of freshwater to the ground-water reservoir of Long Island. Annual precipitation in the Roosevelt Field area averages about 42 inches and is fairly well distributed throughout the year (Miller and Frederick, 1969). Nearly half the annual precipitation is returned to the atmosphere by evapotransporation; the remainder infiltrates the earth's surface and percolates downward to the water table as recharge to the ground-water system (Cohen and others, 1968). Direct runoff of

precipitation from paved areas is routed to recharge basins, which are excavations in the upper glacial deposits from which water infiltrates fairly rapidly into the ground. Direct runoff to streams from precipitation is negligible in the Roosevelt Field area.

Monthly precipitation measured at Mineola (fig. 1) from October 1982 through September 1984 is plotted in figure 4; the bar graph shows that precipitation exceeded the 45-year mean annual precipitation of 43.63 inches during all 3 years of this study. Water year 1984 was particularly wet, especially during the spring.


44.82 inches total
51.93 inches total
70.12 inches total
10
5
0
PRECIPITATION, IN INCHES
45-year
monthly mean
(3.58 in)
O N D J F M A M J J A S O N D J F M A M J J A S O N D J F M A M J J A S
1982
1983
1984
WATER YEAR

Figure 4.--Monthly precipitation at Mineola, N.Y., during 1982-84 water years.

Water Use

Annual pumpage from 11 public-supply wells in the Roosevelt Field area is given in table 2; well locations are shown in figure 5 and plate 1.

Four public-supply wells (N3934, N3935, N5484, and N5485) and seven cooling-water wells (N5507, N6045, N8050, N8068, N8458, N9310, and N9311) pump water from the Magothy aquifer at Roosevelt Field. The public-supply wells may operate all year, but the peak demand for water during summer causes higher pumpage rates from June through September (fig. 6). Daily summer pumpage from the four public-supply wells may exceed 4 Mgal/d during hot, dry

weather. Cooling-water wells operate seasonally 12 to 16 hours per day during warm weather (May-September) and are generally off during cool weather, although well N8458, at the northeast end of the shopping mall, operates intermittently throughout the year. Combined pumpage from the seven cooling-water wells during the cooling season was about 4 Mgal/d in 1984.



Figure 5.--Location of pumping centers and areas of cooling-water discharge at Roosevelt Field in 1983. Prior to 1985, cooling-water wells N5507, N6045, N8050, and N8458 discharged used water to Pembrook basin; wells N9310 and N9311 continue to discharge used water to Garden City Plaza drain field.

Table 2.--Annual pumpage from 11 public-supply wells in the Roosevelt Field area.

[Well locations are shown in pl. 1; data from pumpage records supplied by local water departments]

Well number	Pumpage, in thousands of gallons	
	Water year* 1982	Water year 1983
N2748	126,051	157,123
N3934	217,903	246,824
N3935	241,197	256,208
N5484	114,742	140,334
N5485	102,713	100,986
N5596	251,226	183,047
N7957	209,399	272,453
N8457	165,033	163,993
N8474	238,044	244,302
N8475	255,218	239,570
N9521	203,877	331,299
Total	2,125,403	2,336,139

* Water year is the 12-month period from October 1 of the previous year through September 30 of the indicated year.



Figure 6.

Total monthly pumpage from four public-supply wells at Roosevelt Field during 1983 water year. (Data from daily pumpage records supplied by local water departments.)

Recharge

Most of Roosevelt Field is paved and impervious; thus, natural recharge of the underlying ground-water system is limited to small grassy areas around the perimeter of the shopping center. Storm drains receive runoff from some of the impervious areas and route it to recharge basins; storm drains in paved parking areas are open to the underlying deposits, which allows direct infiltration. When a storm drain's infiltration capacity is exceeded, overflow conduits carry the excess runoff to local recharge basins. The sporadic recharge from precipitation causes short-term rises of the water table and also causes changes in ground-water quality because the storm runoff differs from ground water, which in some areas at Roosevelt Field is contaminated by VOCs.

Disposal of used cooling water from the seven cooling-water wells provides additional recharge to the ground-water system during the cooling season, typically May through September. During 1982-84, used water from four of the wells was discharged to the upper glacial aquifer at a pair of recharge basins, and water from two wells was discharged to a drain field. Water from the other well was discharged to a series of diffusion wells. Locations of discharge sites, described below, are shown in figure 5.

Recharge Basins

Two recharge basins at the southwest corner of Roosevelt Field (fig. 5) received about 2 Mgal/d from four cooling-water wells (N5507, N6045, N8050, N8458 in pl. 1) in 1982-84 as well as public-supply water from the cooling-water-distribution system during summer. The discharge water was contaminated with VOC's pumped from the intermediate depths of the Magothy aquifer, principally at wells N5507 and N8050. The recharge basin that received most of the water, referred to herein as Pembrook recharge basin, is privately owned and is divided by an earth dam into halves that are hydraulically connected by a concrete channel. The basin covers 2.5 acres, is excavated in the outwash deposits, has an overflow outlet, and forms a perennial impoundment of water. During the 1983 summer, as much as 0.8 Mgal/d of water overflowed and entered the second basin, Nassau County stormwater basin 124 (fig. 5). Thus, about 1.2 Mgal/d infiltrated Pembrook recharge basin as a result of cooling-water discharge during hot weather, and the remaining 0.8 Mgal/d infiltrated the Nassau County basin. Stormwater runoff also entered both basins intermittently throughout the year.

Drain Field

The drain field is excavated in the outwash deposits beneath the parking area at an office-building complex north of the recharge basins, as shown in figure 5. It was built in 1982 on the west side of Roosevelt Field adjacent to the Garden City Plaza office buildings and receives about 2 Mgal/d of cooling water from Magothy aquifer wells N9310 and N9311 during warm weather. Water from these wells is also contaminated by VOC's but is treated by aeration to reduce the concentrations before it is discharged to the drain field.

Before the drain field was constructed in 1982, untreated cooling water from wells N9310 and N9311 was discharged to the Pembrook recharge basin. The drain field was constructed to allow diversion of this contaminated water from the basin, which reduced the overflow from Pembrook recharge basin into Nassau County recharge basin 124. Treatment of the water before discharge to the upper glacial aquifer at the drain field entails percolation through a column of plastic baffles in contact with forced air, which strips volatile constituents from the water. During the summer cooling season, about 1.2 Mgal/d is treated and discharged to the drain field.

Diffusion Wells

The diffusion wells are in the southern part of Roosevelt Field and receive about 0.8 Mgal/d from cooling-water well N8068 (fig. 5). This discharge has relatively low VOC concentrations (far below New York State Health Department drinking-water guidelines for VOCs) and is not discussed further herein.

Ground-Water Movement

The regional direction of ground-water movement in this area is southwest from the mid-island ground-water divide (fig. 1), about 2 mi north of Roosevelt Field, to discharge areas at and beyond the south shore in southeastern Queens County and southwestern Nassau County (Donaldson and Koszalka, 1983a, b, c). The water table in this area is in the upper glacial aquifer and lies 25 to 50 ft below land surface. Confined conditions predominate in deeper zones of the Magothy aquifer, where silty and clayey layers form local confining units (Franke and McClymonds, 1972). Flow in this system is predominantly horizontal because the bedding planes are almost horizontal and thus provide less resistance to lateral flow, and because the clayey layers retard vertical flow. The potentiometric surface of deeper aquifer zones at Roosevelt Field is lower than the water table; thus, ground-water movement in this area has a downward component.

Water levels in wells screened in the upper glacial aquifer were measured at least twice yearly during 1982-84. The first measurements each year were made in the spring before the start of cooling-water pumping to delineate flow patterns during periods of near-minimal pumping. Measurements were again made in August, during periods of peak withdrawals for cooling water and public supply, to evaluate the changes induced by pumping stresses, which are primarily in the Magothy aquifer, and by the cooling-water discharges.

Upper Glacial Aquifer

Plate 1 shows the water-table configuration drawn from 61 measurements made on April 25, 1984. April 1984 was a period of minimal ground-water pumping and discharge at Roosevelt Field, and regional flow was south-southwestward (S25°W) and primarily horizontal. The average water-table gradient was 0.0012 ft/ft. The rate of regional horizontal ground-water flow in the upper glacial aquifer during low-stress periods, based on a hydraulic conductivity of 250 ft/d and a porosity of 0.30 (McClymonds and Franke, 1972), is about 1.0 ft/d.

Stormwater runoff and discharged cooling water that enter Pembrook recharge basin cause a water-table mound 1 to 2 ft high that persists throughout the year. This mound was 2 to 4 ft high, however, during warm weather, when up to 4 Mgal/d of spent cooling water is discharged to the basin, as seen in the August 1982-84 water-table maps (figs. 7A, 7B, and 7C).

August 1982 water table.--The water-table map in figure 7A was drawn from 34 measurements made on August 19, 1982. The water-table mounding beneath Pembrook recharge basin was 2 to 3 ft above the regional water table in the



Base from NYSDCT, Freeport, NY, 1981; Lynbrook, NY, 1981; Sea Cliff, NY, 1981; and Hicksville, NY, 1981, 1:24,000

0 1000 2000 FEET
0 300 600 METERS

EXPLANATION

52 — WATER-TABLE CONTOUR--Shows altitude of water-table. Contour interval 2 feet. Datum is sea level

Figure 7A.--Water-table configuration at Roosevelt Field in August 1982. (Location is shown in fig. 1.)

area. Spent cooling water (about 4 Mgal/d) from six wells at Roosevelt Field (N5507, N6045, N8050, N8458, N9310, and N9311, pl. 1) caused overflow into Nassau County basin 124, which eventually infiltrated the basin floor or evaporated.

A slight depression of 1 to 2 ft in the water table is indicated about 1,200 ft north of Pembrook recharge basin (fig. 7A). This is attributed to withdrawal from the Magothy aquifer at wells N9310 and N9311, at the west side of the shopping mall, which are screened 180 to 230 ft below land surface.



Base from NYSDOT, Freeport, NY, 1981; Lynbrook, NY, 1981; Sea Cliff, NY, 1981; and Hicksville, NY, 1981, 1:24,000

Figure 7B.--Water-table configuration at Roosevelt Field in August 1983. (Location is shown in fig. 1.)

Pumpage from these two wells during warm weather is about 1.2 Mgal/d. This is the shallowest withdrawal at Roosevelt Field, and the good hydraulic connection between the upper zone of the Magothy aquifer and the water-table aquifer in this area causes a slight water-table depression. A local reversal in water-table gradient between the depressed area and the mound beneath Pembrook recharge basin was created during the summer of 1982 (fig. 7A). The seasonal flow of ground water from the area of Pembrook recharge basin toward the depressed area against the regional hydraulic gradient is indicated by hydrographs for wells N9955 and N9958 (fig. 8).



Base from NYSDOT, Freeport, NY, 1981; Lynbrook, NY, 1981; Sea Cliff, NY, 1981; and Hicksville, NY, 1981; 1:24,000

EXPLANATION

0 1000 2000 FEET
0 300 600 METERS

—62— WATER-TABLE CONTOUR--Shows altitude of water-table. Contour interval 2 feet. Datum is sea level

Figure 7C.--Water-table configuration at Roosevelt Field in August 1984. (Location is shown in fig. 1.)



Figure 8.--Water-table altitudes at wells N9955 near Pembrook recharge basin and N9958 near Garden City Plaza from August 1982 through January 1983. Higher levels in well N9955 from August through October reflect the discharge of water at nearby Pembrook recharge basin, and lower levels in well N9958 reflect pumping at nearby Magothy wells N9310 and N9311. Effects of pumping and discharge dissipate after October, and the regional water-table gradient again dominates.

August 1983 water table.--The 1983 water-table map (fig. 7B) was drawn from 52 measurements made on August 31, 1983. The mound beneath Pembrook recharge basin was 3 to 4 ft above the regional water table. At this time, cooling water from wells N9310 and N9311 was diverted to the new drain field 1,400 ft north of the recharge basin (fig. 5) rather than to Pembrook recharge basin to alleviate overflow from the basin into Nassau County basin 124. This discharge to the drain field created a new water-table mound 3 to 4 ft high, which was elongated along Clinton Road (fig. 7B). This mound replaced the water-table depression observed in 1982 (fig. 7A).

August 1984 water table.--The 1984 water-table map (fig. 7C) was drawn from 38 measurements made on August 8, 1984. Two mounds are evident, as in August 1983 (fig. 7B). The mound beneath Pembrook recharge basin was 2 to 3 ft above the regional level, and the one beneath the drain field was 4 to 5 ft

above the regional level. A small decrease in the height of the mound beneath the basin and an increase in the mound height beneath the drain field from August 1983 (fig. 7B) to August 1984 (fig. 7C) probably resulted from the diversion of discharge water from wells N9310 and N9311 from the basin after initial operation of the drain field in August 1983. In 1984, all water (2.1 Mgal/d) from these wells was discharged to the drain field.

Magothy Aquifer

The potentiometric surface of the Magothy aquifer was measured in conjunction with water-table measurements in April 1982-84, when most pumping wells had been idle for at least 48 hours. The horizontal hydraulic gradient in April 1984 was about 0.0013 ft/ft, and flow was generally west-southwestward. The potentiometric-surface configuration of the Magothy aquifer is similar to that of the water table in the upper glacial aquifer when pumps are off, but heads in the Magothy aquifer are generally 1 to 2 ft lower than the water table, and flow is slightly more westward. The rate of horizontal flow at Roosevelt Field, based on a hydraulic conductivity of 56 ft/d and effective porosity of 0.30 (McClymonds and Franke, 1972), averages about 0.3 ft/d, but rates may range from negligible to 0.6 ft/d. This average flow rate represents only nonpumping conditions, however.

The potentiometric-surface altitude during periods of summer pumping could not be determined because most wells used for measurement were being pumped. The surface is apparently uneven because localized depressions that may exceed 50 ft in depth develop and recover in response to variable pumping schedules for cooling water and public supply. Water-level measurements at wells about 1,000 ft from several pumping centers in the Magothy aquifer indicated that heads there were 2 to 4 ft lower than the water table during warm-weather pumping.

Downward Movement of Water in the Aquifer System

Hydraulic-head measurements in clusters of wells having screens set at different depths were used to evaluate daily and seasonal fluctuations in vertical hydraulic gradient, which reflect pumping and recharge and also the hydraulic conductivity between screened zones. Ground water has a downward flow component beneath all of Roosevelt Field. The downward component results from hydraulic heads in the middle and basal sections of the Magothy aquifer that are lower than hydraulic heads in the upper glacial aquifer. The vertical hydraulic gradient generally increases considerably during warm weather, when heads in the Magothy aquifer are lowered by cooling-water and public-supply withdrawals and when mounds of discharge water in the upper glacial aquifer are highest. Thus, the rates of vertical ground-water movement are greatest during summer periods of peak water demand and cooling-water discharge.

The influence of withdrawals from the Magothy aquifer on vertical gradients during warm weather at Roosevelt Field is illustrated in hydrographs (fig. 9) for wells N9955 and N10020, near the southwest corner of the shopping center. Well N9955 is screened in the upper glacial aquifer, 35 ft above sea level; well N10020 is screened in the upper part of the Magothy aquifer, 107

ft below sea level. The 1982 hydrographs (left side of fig. 9) represent September 7 to October 5, a period of warm weather. Combined public-supply and cooling-water pumpage from the Magothy aquifer within 1,500 ft of the well cluster was about 6.5 Mgal/d. During this period, the water table in the upper glacial aquifer (N9955) gradually declined but had daily fluctuations of about 0.1 ft due in part to recharge at the nearby Pembrook recharge basin. In contrast, The potentiometric surface in the Magothy aquifer (N10020) during this period fluctuated nearly 3.0 ft daily. The maximum vertical hydraulic gradient between screened zones at these two wells during this period was 0.032 ft/ft on September 13. The minimum gradient, when pumps were off, was 0.008 ft/ft on September 18.

The influence of public-supply withdrawals from the Magothy aquifer on vertical gradients at Roosevelt Field during cool weather is seen in the hydrographs on the right side of figure 9, which depicts water levels from February 18 through March 20, 1983. The only pumping in the area at that time was public-supply withdrawal of about 1 Mgal/d at two wells (N3934 and N3935), 900 ft west of N9955 and N10020. The water-table altitude generally increased during this time, and no daily fluctuations are apparent, although recharge from several storms is evident. In contrast, the potentiometric surface in the Magothy aquifer fluctuated by about 1 ft daily in response to the



Figure 9.--Water-level fluctuations at wells N9955 and N10020, near southwest corner of shopping center: Left, during a month of warm weather in fall 1982. Right, during a month of cool weather in winter 1983. (Well locations are shown on pl. 1.)

public-supply pumping. The maximum vertical hydraulic gradient between screened zones of the two wells during this period was 0.014 ft/ft on March 19, and the minimum observed gradient was 0.004 ft/ft when pumps were off on March 2. In general, the mean vertical gradient during the cool-weather period was about half that during the warm-weather period. Accordingly, average vertical flow rates in March 1983 at this well site were about half the average vertical flow rate in September 1982.

Inorganic Chemical Constituents in Ground Water

Inorganic chemical constituents and physical characteristics were measured in 183 samples from 105 wells screened in the upper glacial and Magothy aquifers; the results are summarized in table 3. Dissolved oxygen (DO), which indicates oxidizing conditions, was detected at most wells, and specific conductance values were generally low, ranging from 33 to 850 µS/cm (microsiemens per centimeter at 25°C). The median specific conductance in the upper glacial aquifer was 250 µS/cm and in the Magothy aquifer was 97 µS/cm. Median pH in the upper glacial aquifer was 6.2 and in the Magothy aquifer was 5.8. The median alkalinity in the upper glacial aquifer was 20 mg/L (as $CaCO_3$) and in the Magothy aquifer was 6 mg/L. In general, median concentrations of inorganic chemical constituents were consistently lower in the Magothy aquifer than in the upper glacial aquifer (table 3), except silica.

Water from the Magothy aquifer generally has lower concentrations of inorganic chemical constituents than water from the upper glacial aquifer, presumably because water from the Magothy aquifer is older and reflects the less urbanized conditions of the past. Dilution and dispersion in the Magothy aquifer also reduce concentrations of constituents that originated at land surface and moved through the upper glacial aquifer. The differences in median concentrations of inorganic chemical constituents between the two aquifers are small, however, and the discharge of cooling water pumped from the Magothy aquifer does not significantly alter the concentrations of constituents in the upper glacial aquifer.

Dissolved iron and manganese and total nitrate concentrations were the only inorganic chemical constituents that exceeded New York State drinking-water standards. Dissolved iron concentrations exceeded drinking-water standards in 40 percent of the wells sampled, and manganese concentrations exceeded the standards in 27 percent, probably because of localized reducing environments. The median nitrate concentration was 3.8 mg/L (as N) in the upper glacial aquifer and 3.6 mg/L in the Magothy aquifer, but the difference was not statistically significant (α equals 0.05). Elevated nitrate concentrations in the Magothy aquifer may have originated from agricultural fertilizers and septic-waste disposal before ex-tensive development of the area, whereas nitrate in the upper glacial aquifer may have originated from more recent sources such as lawn fertilization in medium- to high-density suburban areas (Katz and Lindner, 1978). Nitrate exceeded drinking-water standards in 6 percent of all wells sampled. Public-supply wells N2747, N5654, and N6046 (not sampled), which tap the Magothy aquifer in the Roosevelt Field area, have had excessive nitrate concentrations and as a result are unused.

Table 8.--Summary of inorganic chemical analyses of ground water from wells in the Roosevelt Field area of Nassau County, 1984

[All concentrations are in milligrams per liter]

Constituent or property[1]	Number of samples	Concentration or value				
		Minimum	10th percentile	Median	90th percentile	Maximum
A. Wells screened in upper glacial aquifer						
Total dissolved solids	53	64.	79.	171.	335.	487.
Specific conductance (µS/cm at 25°C)	53	92.	130.	250.	423.	850.
pH	53	4.4	5.5	6.2	6.6	6.8
Alkalinity (as $CaCO_3$)	52	1.	5.	20.	37.	65.
Nitrite (NO_2 as N)	53	< .001	.002	.008	.041	.481
Nitrate (NO_3 as N)	52	< .10	.63	3.8	7.8	15.
Total hardness (as $CaCO_3$)	53	12.	24.	66.	330.	650.
Calcium (Ca)	53	2.9	5.0	14.	35.	41.
Magnesium (Mg)	53	1.1	1.6	3.5	9.7	18.
Sodium (Na)	52	5.0	9.0	22.	49.	130.
Potassium (K)	53	.3	.9	2.4	5.1	8.4
Chloride (Cl)	53	7.5	13.	39.	78.	246.
Fluoride (F)	53	< .2	< .2	< .2	< .2	0.2
Sulfate (SO_4)	52	<5.	<5.	24.	72.	81.
Iron (Fe)	53	< .05	< .05	.43	5.3	9.3
Manganese (Mn)	53	< .05	< .05	< .05	.83	2.8
Silica (SiO_2)	53	1.3	3.1	5.7	8.1	8.6
B. Wells screened in Magothy aquifer						
Total dissolved solids	54	29.	36.	64.	188.	302.
Specific conductance (µS/cm at 25°C)	54	33.	46.	97.	334.	533.
pH	54	4.9	5.3	5.8	6.2	7.0
Alkalinity (as $CaCO_3$)	54	1.	2.	6.	12.	25.
Nitrite (NO_2 as N)	54	< .001	< .001	.002	.015	.030
Nitrate (NO_3 as N)	54	< .10	.55	3.6	9.6	13.
Total hardness (as $CaCO_3$)	54	7.	9.5	22.	67.	111.
Calcium (Ca)	54	1.3	2.2	5.5	17.	27.
Magnesium (Mg)	54	.4	.5	2.4	5.0	10.
Sodium (Na)	54	<3.	3.0	8.0	28.	85.
Potassium (K)	54	.2	.5	.9	1.8	5.7
Chloride (Cl)	54	3.5	5.4	11.	51.	166.
Fluoride (F)	54	< .02	< .2	< .2	< .2	< .2
Sulfate (SO_4)	54	<5.	<5.	6.	26.	77.
Iron (Fe)	42	< .05	< .05	< .05	.88	5.2
Manganese (Mn)	42	< .05	< .05	< .05	.07	.40
Silica (SiO_2)	54	4.4	5.4	6.9	9.4	14.

[1] All constituents are total concentrations from unfiltered samples, except for iron and manganese, which are dissolved concentrations from filtered (0.45-µm membrane) samples.

Ground-Water Temperature

The median ground-water temperature at wells in the Roosevelt Field area, excluding those affected by cooling-water discharge, was 11°C; the range was from 10°C to 15°C. Ground-water temperature fluctuated strongly with season in wells adjacent to the Pembrook recharge basin. In well N10097, near the basin, water temperature ranged from 7.3°C (May 1984) to 22.6°C (September 1984), reflecting cold storm-runoff water during the winter and water warmed by air conditioning in the summer. Ground-water temperature at other wells near the basin, N9966 and N10096, indicated similar seasonal effects in response to the discharge of cooling water.

VOLATILE ORGANIC COMPOUNDS IN GROUND WATER

Chemical Character

Volatile or purgeable organic compounds generally are defined as low-molecular-weight hydrocarbons having less than 2-percent solubility in water and boiling points below 150°C. Most are liquid at room temperature. Some common priority pollutants (U.S. Environmental Protection Agency, 1979b) include vinyl chloride, trichloroethylene, tetrachloroethylene, chloroform, carbon tetrachloride, benzene, toluene, and chlorobenzene. Each is considered toxic to some degree, and most, including TCE, are believed to be carcinogenic (National Academy of Sciences, 1977). The U.S. Environmental Protection Agency (1979b, c) has described and assessed TCE and other VOC's in the environment and discussed their transport and fate in ground water.

The physical properties of TCE are typical of chlorinated aliphatic VOC's. It is a colorless liquid with a density of 1.46 g/mL (grams per milliliter) at 20°C. It has a molecular weight of 131, a boiling point of 87°C, and a solubility in water of 1,100 mg/L (about 1/10 percent by weight). The structural configuration of TCE is:



The compounds listed above are used primarily as solvents. Typical sources of these compounds include dry-cleaning fluids, degreasing solvents, organic drain cleaners, furniture-refinishing compounds, and gasoline or other fuels. TCE has been in commercial use less than 40 years. The New York State Health Department guidelines in 1984 for maximum concentrations in drinking water were 5 µg/L for vinyl chloride and benzene, 50 µg/L for each of the remaining VOC's, including TCE, and 100 µg/L for total VOC concentration.

The solubilities of VOC's in ground water are very low, and the loss of VOC's from solution to clean air occurs readily. Conversely, clean water exposed to air containing a volatile organic compound in gaseous form can rapidly accumulate detectable levels of the compound in solution, and false-positive tests resulting from this phenomenon are common in analytical laboratories where solvents are frequently used. Thus, extensive precautions

must be taken in collection and storage of ground-water samples intended for VOC analysis. Exposure to air must be minimized during sample collection, and sample bottles must be filled to the top and sealed to eliminate exposure to gas phases and are chilled for storage. They have a finite shelf life.

Concentrations at Roosevelt Field

The principal VOC in ground water at Roosevelt Field is trichloroethylene (TCE); *cis*-1,2-dichloroethylene (DCE) and tetrachloro-ethylene (PCE) occur in lesser concentrations. (See tables 7 and 8, at end of report.) Trichloroethylene was found in 44 percent of the wells sampled throughout the Roosevelt Field area in 1984, and the maximum concentration was 38,000 µg/L. Tetrachloroethylene was detected in 46 percent of the wells sampled, and the maximum concentration was 350 µg/L. *cis*-1,2-Dichloroethylene was detected in 21 percent of the wells sampled, the maximum concentration was 2,800 µg/L. TCE, DCE, and tetrachloroethylene were detected in August 1984 in the combined outflow from three cooling-water wells that tap the Magothy aquifer (N5507, N8050, and N8458); this water was discharged after use to Pembrook recharge basin. TCE, DCE, and minor amounts of tetrachloroethylene were also detected in the combined outflow from the two cooling-water wells (N9310 and N9311) that discharge water after use to the Garden City Plaza drain field.

Forty water samples from 28 public-supply wells were also collected in 1983 and 1984 (table 8). VOC's were detected in 9 wells, 4 of which contained more than 25 µg/L total VOC's. Ground-water samples from public-supply wells N3934 and N3935 (owned by the Village of Garden City) and N5484 and N5485 (owned by the Town of Hempstead) in April 1984 contained 22, 27, 13, and 26 µg/L, respectively, of total VOC's, principally TCE. A sample from well N83 (owned by the Village of Hempstead) in April 1984 contained 29 µg/L of TCE and 15 µg/L of tetrachloroethylene. All samples from public-supply wells met New York State Health Department drinking-water guidelines of 50 µg/L for individual VOC's.

VOC concentrations in excess of drinking-water guidelines have been detected in several monitoring wells not associated with the TCE at Roosevelt Field. Samples obtained in spring 1984 from wells N1160, N9703, and N9803 southeast of Roosevelt Field (pl. 2) contained 53 µg/L of 1,1,1-trichloroethane, 260 µg/L of *cis*-1,2-dichloroethylene, and 280 µg/L of 1,1,1-trichloroethane, respectively. Gasoline was detected in water from well N9951 at the northwest corner of Roosevelt Field in August 1983, but in April 1984, after the well screen was raised 10 ft to a shallower zone in the upper glacial aquifer, none was detected. In addition, trace amounts of chloroform, carbon tetrachloride, and other volatile compounds were detected as isolated occurrences throughout the study area.

Trichloroethylene (TCE), 1,2-Dichloroethylene, and Tetrachloroethylene in Discharged Cooling Water

Of seven cooling-water wells at Roosevelt Field, five yield contaminated water from the Magothy aquifer, which is discharged after use to the upper glacial aquifer at the Garden City Plaza drain field and the Pembrook recharge basin (fig. 5). Water from wells N9310 and N9311 at Garden City Plaza has

created a plume of TCE and DCE at the drain field; the contaminants had reached monitoring wells N8666, N9953, N9954, N9964, N9971, N9972, N9973, N9974, and N10095 (pl. 1) by 1984. At Pembrook recharge basin, water discharged from nearby cooling-water wells N5507, N8050, and N8458 created a plume of TCE, DCE, and tetrachloroethylene that had reached wells N9954, N9955, N9965, N9966, N10096, N10035, N10097, N10204, and N10205 by 1984. These two plumes of contaminated discharge water overlie and partly obscure the original plume of VOC's in the upper glacial aquifer.

Discharge to Pembrook Recharge Basin

Samples for VOC analysis were collected, and discharge rates measured, on August 7, 1984, at (1) the four cooling-water wells that discharged to Pembrook recharge basin, (2) the basin's inflow and outflow culverts and midpoint, and (3) three monitoring wells around the basin. The same was done the next day at (1) the two cooling-water wells that discharged to the Garden City Plaza drain field, (2) the inflow and outflow of the aeration facility, and (3) four monitoring wells near the drain field. Discharges of TCE, DCE, and tetrachloroethylene at each point were computed by multiplying flow rate by the concentration and converting the units to pounds of VOC per day, assuming an average 12-hour pumping and discharge duration. The data are presented in table 4. The values for each well represent the rate of withdrawal of each contaminant from the Magothy aquifer; the values for the recharge basin and drain field represent the rate of return to the upper glacial aquifer.

About 19 lb/d of TCE and 2.7 lb/d of tetrachloroethylene were removed from the Magothy aquifer by pumping at wells N5507, N8050, and N8458, on the assumption that flow rate and concentrations were constant (table 4). About 13 lb/d of TCE (principally from well N8050) and 3.2 lb/d of tetrachloroethylene (principally from well N5507) were discharged to Pembrook recharge basin. About 500 gal/min of public-supply water augmented the cooling-water supply and diluted the discharge. Flow rates and water-quality samples collected at the midpoint of Pembrook basin, where a berm separates the basin into a north and a south section, indicate that the south section has higher infiltration rates than the north section but lower concentrations of TCE. About 2.5 lb/d of TCE was discharged in the 1,200-gal/min outflow from Pembrook basin and entered Nassau County basin 124 through a connecting culvert.

Samples from monitoring wells around Pembrook recharge basin directly reflect the quality of water infiltrating the basin. Cooling-water well N5507 and monitoring wells around the basin contained significant concentrations of tetrachloroethylene. This serves as an indicator for distinguishing between water discharged to the recharge basin, other contaminant plumes, and ambient ground water at Roosevelt Field.

Discharge to Garden City Plaza Drain Field

About 18 lb/d of TCE and 3 lb/d of DCE is removed from the Magothy aquifer by pumping at wells N9310 and N9311, near the drain field, assuming constant flow rates and TCE concentrations for the 12-hour pumping day (table 4). The contaminated cooling water is piped in a closed system to the treatment

facility at 100 Garden City Plaza, where it is aerated and discharged to the nearby drain field. Comparison of TCE concentrations before and after aeration indicated 44-percent removal by the treatment in August 1984; the discharge contained 9.6 lb/d of TCE and 1.3 lb/d of DCE. Samples from monitoring wells N9971, N9972, and N9973 at the drain field directly reflect the concentrations in the discharge water. The lack of either compound at well N9974, 600 ft southeast of the drain field, indicates that this well was beyond the influence of the discharge.

Table 4.--Concentration and discharge of volatile organic compounds in water from six cooling-water wells at Roosevelt Field, August 1984

[Discharge points and well locations are shown in fig. 5; dashes indicate data unavailable]

Discharge location	Screen setting (feet below land surface)	Flow rate (gal/min)[a]	Concentration (micrograms per liter)			Discharge (pounds per day)[b]		
			1,2-di-chloro-ethylene	tri-chloro-ethylene	tetra-chloro-ethylene	1,2-di-chloro-ethylene	tri-chloro-ethylene	tetra-chloro-ethylene
A. AT PEMBROOK BASIN								
Contributing wells								
N5507[c]	107 - 108 157 - 168 295 - 330	1,200	(d)	380	350	(d)	2.7	2.5
N6045	271 - 322	800	(d)	3	3	(d)	.01	.01
N8050	300 - 328	200	1,100	13,000	47	1.3	16.	.06
N8458	290 - 350	800	(d)	37	21	(d)	.18	.10
Recharge basin								
basin inflow	--	3,500	41	600	150	.86	13.	3.2
basin midpoint	--	2,600	24	380	120	.38	5.9	1.9
basin outflow	--	1,200	17	340	100	.12	2.5	.72
Monitoring wells								
N9966	48 - 54	--	28	350	97	--	--	--
N10096	35 - 36	--	40	370	110	--	--	--
N10097	35 - 36	--	17	300	80	--	--	--
B. AT DRAIN FIELD								
Contributing wells								
N9310	180 - 230	800	73	810	19	.35	3.9	.09
N9311	189 - 229	800	530	3,000	10	2.5	14	.05
Drain field								
Untreated inflow	--	1,600	270	1,800	15	2.6	17	.14
Treated outflow	--	1,600	130	1,000	3	1.3	9.6	.03
Monitoring wells								
N9971	35 - 40	--	130	560	3	--	--	--
N9972	35 - 40	--	100	360	(d)	--	--	--
N9973	35 - 40	--	130	550	5	--	--	--
N9974	30 - 35	--	(d)	1	(d)	--	--	--

[a] Gallons per minute.
[b] Computation of contaminant discharge based on a 12-hour pumping day.
[c] Well has multiple screens.
[d] Less than detection limit.

TCE in the Upper Glacial Aquifer

Three plumes of trichloroethylene contamination have been delineated in the upper glacial aquifer at Roosevelt Field, two of which consist of discharge water overlying the original plume.

Original Plume

The northernmost (furthest upgradient) extent of the original plume is at wells N8666, N9953, and N9971, as indicated by water-quality samples collected before discharge to the drain field began in 1982; thus, the source of the contamination is probably within or slightly upgradient of the area near the site of aircraft-maintenance hangars when the airfield was closed in 1951 (fig. 2A).

The original plume has moved horizontally downgradient in the upper glacial aquifer and downward into the Magothy aquifer. Its extent is obscured by the overlying plumes of contaminated cooling-water discharge, but historical data from 1981 (table 7, at end of report) indicate that it intersected wells in the upper glacial aquifer at Garden City Plaza--N8666, N9971, N9972, and N9974--where the drain field is now located. June 1982 data from wells installed after the 1981 sampling, summarized below, indicate that the original plume was also affecting wells N9954 and N9964, southwest and downgradient of Garden City Plaza, and was bounded by wells N9953, N9958, and N9965 on the west and east sides of Garden City Plaza.

		Concentration (µg/L)		
Well	Date	DCE	TCE	PCE
N8666	3-17-81	<5	120	1
N9954	6-17-82	30	220	21
N9964	6-18-82	<7	30	11
	6-24-82	16	120	24
N9971	8-13-81	<5	10	<1
N9972	8-13-81	<5	15	<1
N9974	8-13-81	<5	19	9

These data indicate the location of the original plume and its south-southwestward direction of horizontal movement, parallel to the main direction of regional ground-water flow in the upper glacial aquifer.

Plume at Garden City Plaza Drain Field

Since September 1982, the discharge of cooling water originating from wells N9310 and N9311, near the drain field (fig. 5), has contained VOC's in concentration up to 1,000 µg/L, even after treatment by aeration. Samples from November 1982 (table 7, at end of report) indicate that initially the contaminated water extended west of the drain field and affected well N9953 (210 µg/L of TCE), which had been previously free of VOC's, and wells N9954 (110 µg/L TCE) and N9964 (360 µg/L TCE), southwest and downgradient of the drain field, which had been previously contaminated by the original plume.

The newly affected wells reflect the extent of radial flow as contaminated discharge water moves away from the seasonal water-table mound created beneath the drain field (fig. 7b, 7c).

Samples from August 1983 and April 1984 indicate that TCE concentrations in the area of the original plume fluctuate in response to the seasonal discharge of cooling water from wells N9310 and N9311 and also from dilution by natural recharge. Significant TCE concentrations were detected in August 1983, near the end of the summer cooling season, in wells N9953, N9954, N9964, and N9965, as shown below (data are from table 8, at end of report).

		Concentration (µg/L)		
Well	Date	DCE	TCE	PCE
N9953	8- 4-83	84	480	3
	4-30-83	<4	56	3
N9954	8- 2-83	61	480	50
	4-17-83	<4	92	31
N9964	8- 8-83	62	290	410
	4-19-84	<4	20	27
N9965	8- 4-83	120	670	4
	4-23-84	70	320	1

Much lower TCE concentrations were observed in the same wells in April 1984, after 7 months without cooling-water discharge. The data from April 1984 reflect the presence contaminated discharge of cooling water from the prior year, which had been diluted by natural recharge and dispersed during the preceding winter.

Plume at Pembrook Recharge Basin

The second discharge plume, which originates at Pembrook recharge basin (fig. 5), overlies the two other plumes that have sources farther upgradient. Prior to 1985, cooling water contaminated by VOC's was discharged to this basin from wells N5507, N6045, N8050, and N8458 12 to 16 hours per day during warm weather. Storm runoff, which was free of VOC's, intermittently entered the basin and diluted the contaminated water. During dry summer weather, TCE concentrations in the basin remained high because of the daily discharge of contaminated cooling water; however, when the cooling-water pumps are off during winter and spring, TCE concentratons were reduced to the detection limit because only storm runoff entered the basin.

The seasonal changes in chemical quality of basin water are reflected at monitoring wells around the basin. Analyses of samples from wells N9966, N10096, and N10097 (on next page; data are from table 8) indicate this annual cyclic trend. Concentrations of VOCs were high in the summer of 1983 and low in the spring of 1984, which reflects dilution by the inflow of storm runoff during the preceding winter.

The August 1984 water-table map (fig. 7C) indicates that recharge at the basin also influences water at wells N9955 and N9964, which are about 300 ft north and 150 ft west of the basin, respectively. Well N9955, although

Well	Date	Concentration (µg/L) DCE	TCE	PCE
N9966	8- 8-83	40	320	55
	4-16-84	<4	3	1
N10096	8-25-83	80	300	44
	5- 1-84	<4	19	1
N10097	8-17-83	45	250	39
	5- 7-84	<5	2	<1

strongly influenced, shows a lag in the seasonal appearance of TCE because it is farther from the basin. Mounding of the water table below the basins (figs. 7a-7c) caused a reversal of the regional hydraulic gradient in the water table (fig. 8) and resulted in a delayed seasonal appearance of TCE in well N9955 (510 µg/L in November 1982, 5 µg/L in August 1983, and 440 µg/L in April of 1984.

Tetrachloroethylene (observed mainly in water from cooling-water wells N5507 and N8050 and discharged to Pembrook recharge basin after use) was used to distinguish the plume originating at the recharge basins from that originating at the drain field, which contains relatively low concentrations of tetrachloroethylene. The two discharge plumes have merged in the upper glacial aquifer near Clinton Road Water Works (public-supply wells N3934 and N3935, screened in the Magothy aquifer and owned by the village of Garden City), directly west of Pembrook recharge basin.

TCE was detected hydraulically downgradient of the recharge basins in April and May 1984 at wells N5725 (140 µg/L), N6949 (12 µg/L), N10204 (210 µg/L), N10205 (81 µg/L), and N10035 (70 µg/L) (pl. 1). The seasonal fluctuation in quality of water from the basins is not readily apparent in data from well N10035, 1/2 mi downgradient; evidently this distance is sufficient for dispersion and dilution to create a more homogeneous distribution of TCE. No TCE was detected in well N9398, 1 mi downgradient of the recharge basin.

Extent of TCE Contamination

The distribution of TCE (fig. 10a) in the upper glacial aquifer was plotted from 28 water samples collected from August 1 through September 30, 1983, a period of heavy pumping. TCE and *cis*-1,2-dichloroethylene show a similar distribution, but TCE concentrations are higher, as shown in table 8 (at end of report). The highest concentrations of TCE (as high as 670 µg/L at well N9965) are associated with discharge of contaminated cooling water to the drain field. The TCE plume from Pembrook recharge basin adjoins the plume from the drain field, and both obscure the original plume. Although radial flow from water-table mounding has moved the TCE in all directions beneath both discharge sites (fig. 7C), the plumes have dispersed south-southwestward along the main direction of regional ground-water movement in the upper glacial aquifer.

The distribution of TCE in the upper glacial aquifer in April 1984, a period of light pumping (fig. 10b), was determined from 33 samples collected

from April 2 to May 30, 1984. (See table 8.) Both plumes have basically the same configuration as in August 1984 (fig. 10a), but concentrations at the drain field and the basin are significantly lower as a result of recharge with TCE-free storm runoff between October 1983 and April 1984 and the dispersion of TCE-contaminated water discharged during the preceding summer.



Figure 10A.--Trichloroethylene concentrations in the upper glacial aquifer at Roosevelt Field, August-September 1983, a period of heavy cooling-water pumping.

TCE in the Magothy Aquifer

The spatial distribution of TCE in the Magothy aquifer (fig. 11) is less accurately delineated than in the upper glacial aquifer for several reasons. The Magothy aquifer is about 500 ft thick at Roosevelt Field and is considerably more heterogeneous and anisotropic than the upper glacial aquifer, which has about 20 to 50 ft of saturated thickness. Fewer wells in



Base from NYSDOT, Freeport, NY, 1981; Lynbrook, NY, 1981; Sea Cliff, NY, 1981; and Hicksville, NY, 1981, 1:24,000

Figure 10B.--Trichloroethylene concentrations in the upper glacial aquifer at Roosevelt Field, April-May 1984, before start of seasonal cooling-water pumping.

the area tap the Magothy aquifer (total of 12) than the upper glacial aquifer (total of 25), and the wells are screened at variable depths (public-supply wells are screened deeper than 370 ft, whereas cooling-water supply and monitoring wells are screened less than 330 ft deep). In general, however, contaminated water in the Magothy aquifer has been advected and dispersed south-southwestward along regional flow lines. Regional horizontal flow rates in the Magothy aquifer are less than one-third those in the upper glacial aquifer, and vertical flow rates are considerably lower because of anisotropy,



Figure 11.--Trichloroethylene concentrations in the Magothy aquifer at Roosevelt Field, April-May 1984, before start of seasonal cooling-water pumping.

which accounts for the smaller plume (fig. 11). Also, seasonal pumping of wells for cooling water and drinking water at Roosevelt Field decreases and in some areas reverses regional hydraulic gradients near the pumping centers, thereby retarding southwestward plume movement.

The highest concentrations of TCE (and also DCE and tetrachloroethylene) observed during the 3-year study were in cooling-water wells that seasonally pump water from intermediate depths (200 to 350 ft below land surface) in the Magothy aquifer. High TCE concentrations in three cooling-water wells--N8050, N9310, and N9311--indicate that the source of VOC contamination was northeast of these wells. The wells contained 38,000, 1,300, and 550 µg/L TCE respectively, in April 1984 (table 8), which define the highest concentrations in figure 11. A fourth cooling-water well, N5507, located 1,000 ft southeast of N8050, contained 440 µg/L TCE and 140 µg/L tetrachloroethylene in April 1984; the tetrachloroethylene at this well indicates a probable second source of VOC contamination at Roosevelt Field (fig. 11), but no other data verify this.

Four public-supply wells at Roosevelt Field--N3934, N3935, N5484, and N5485, screened between 370 and 572 ft in the Magothy aquifer--contained 11 to 22 µg/L TCE in April 1984. A former public-supply well--N5486, directly east of Garden City Plaza--contained up to 170 µg/L TCE in February 1980 and for this reason was subsequently abandoned and destroyed. Geophysical and lithologic logs at well N5486 indicate an absence of clay layers through the 511-ft thickness of Magothy aquifer at that location. The lack of confining layers provided a favorable pathway for the downward movement of organic contaminants from the source area to deeper zones in the Magothy aquifer. This is discussed in more detail in the following section, "Movement of TCE."

Contamination of shallow zones in the Magothy aquifer beneath the recharge basins and the drain field has probably resulted from the mounding of contaminated discharge water in the upper glacial aquifer, especially where the aquifers are in good hydraulic connection near cooling-water wells and discharge sites. Mounding increases vertical hydraulic gradients, which increases the rates of downward movement of contaminated water into the Magothy aquifer. The lack of observation wells in shallow zones of the Magothy aquifer beneath the discharge areas prevents delineation of the extent of downward movement of contamination from cooling-water discharge, however.

Movement of TCE

Advection, density-induced movement, dispersion, biochemical transformation, volatilization, and adsorption are the primary processes that affect organic-solute transport in ground water. At Roosevelt Field, regional hydraulic gradients and, to a lesser degree, gradients induced by pumping stresses, provide the dominant forces for the advective movement of organic compounds in ground water. The effects and rates of dispersion, biochemical transformation, and adsorption, which diminish concentrations of organic solutes, are less clearly defined but have been discussed by Anderson (1984), Cherry and others (1984), McCarty and others (1981), and Roberts and others (1982).

Advection

Advective movement of an organic contaminant in ground water is the transport of the chemical with flowing water. The rate of transport is proportional to the average ground-water velocity, which is determined by the hydraulic gradients, the hydraulic conductivity, and the porosity of the aquifer material. In the absence of pumping, advective movement of organic solutes in the aquifer system at Roosevelt Field follows regional flow patterns--primarily horizontal but with a small vertical component. The ratio of the horizontal component of advection to the vertical component is directly related to the anisotropy (the ratio of horizontal to vertical hydraulic conductivity, K_h:K_v), which may range from 5:1 to 24:1 in the upper glacial aquifer (Lindner and Reilly, 1983, p. 2) and from 30:1 to 60:1 in the Magothy aquifer (Getzen, 1977).

Seasonal pumping of water from the Magothy aquifer for public supply and cooling water has altered regional gradients, however, so that contaminants in shallow aquifer zones have moved downward toward screen zones in the wells deeper in the aquifer system. Reilly (1978) and Philips and Gelhar (1978) have shown that the major factors that affect the downward advective transport rate are hydraulic characteristics of the aquifer (including anisotropy), screen location and length, pumping rate, and regional hydraulic gradient. For deeply screened wells, the most rapid downward advective movement of contaminants is in aquifer zones where the K_h:K_v ratio is lowest and pumping rates highest.

Upper glacial aquifer.--Ground water in the upper glacial aquifer moves south-southwestward along the regional water-table gradient with a mean velocity of about 1.0 ft/d; flow within the 20- to 40-ft thickness of saturated upper glacial sand and gravel at Roosevelt Field is predominantly horizontal. Local water-table gradients are considerably greater than the regional gradients where mounding from cooling-water discharge occurs. Discharge water, which contains dissolved organic contaminants, moves radially outward from the center of each mound, and local horizontal velocities may exceed 10 ft/d when the mound is 3 to 5 ft above the normal water table. The increased gradients associated with mounding dissipate rapidly with distance from the mounds, and at distances more than 1,000 ft from each discharge site, the movement of contaminated ground water is controlled mainly by regional gradients. Mounding also increases vertical velocities below each mound, which probably results in significant downward movement of contaminated water into the Magothy aquifer. The rates of downward movement are greatest where permeable sandy zones in the Magothy aquifer are in direct hydraulic contact with the upper glacial deposits (K_h:K_v ratio is relatively low); clay zones in the top of the Magothy aquifer impede downward movement because the K_h:K_v ratio is highest in these zones.

Magothy aquifer.--Regional rates of ground-water movement in the Magothy aquifer are considerably lower than in the upper glacial aquifer, and the advective movement of organic contaminants is accordingly much slower. Horizontal ground-water velocity in the Magothy aquifer may range from negligible in clay to about 0.6 ft/d in sand under normal hydraulic gradients; average velocity is about 0.3 ft/d, or one-third the average velocity in the upper glacial aquifer. When gradients are increased by pumping withdrawals, however, ground-water velocity increases proportionally. The velocity

distribution in the Magothy aquifer, especially in deeper zones, is much less uniform than in the upper glacial aquifer because large intermittent withdrawals for public supply and cooling water create highly variable gradients spatially and temporally. The variability is greatest when all 11 deep-well pumps are operating on differing schedules during a typical summer day at Roosevelt Field. Under these conditions in 1983-84, rates of water movement from shallow to deeper zones in the Magothy aquifer was at least doubled at monitoring wells 900 ft from one pumping center (fig. 9) and was more than doubled in sandy zones closer to the screens of pumping wells.

Anisotropy in the Magothy aquifer is greater than in the upper glacial aquifer, primarily because the Magothy Formation contains extensive clay layers that impede the downward movement of water. These layers are discontinuous, however, and the more permeable, coarse-grained deposits surrounding them can provide pathways for downward movement of solutes. The geologic log of well N5486, where the deepest contamination in the Magothy aquifer was observed east of Garden City Plaza, indicates sandy zones without clay layers throughout the thickness of the aquifer. This well is near a source of contamination possibly associated with the Roosevelt Field commercial airfield, before 1950. The high vertical hydraulic conductivity in this area of heavy pumping has allowed higher-than-normal rates of vertical movement of water (and dissolved contaminants) during pumping periods. During peak demand for ground water in the summer (1982-84), about 6.2 Mgal/d of water was pumped from middle and basal sections at Roosevelt Field. Although pumping stresses were not continuous (fig. 9), the transient increases in downward movement of water have become significant over time. Under predevelopment flow conditions (unaffected by man's activities), recharge to the aquifer system from precipitation at Roosevelt Field would mostly follow the lateral gradients and would not reach 500 ft below land surface until far from the Roosevelt Field area (Franke and Cohen, 1972, p. 273). The presence of TCE and DCE 500 ft below land surface at well N5486 indicates that the natural flow patterns and contaminant movement in the aquifer system in this area have been significantly altered by pumping.

Density-Induced Movement

Density-induced downward movement of undissolved heavy organic solvents may partly account for the presence of TCE in the basal section of the Magothy aquifer at Roosevelt Field. TCE is about 1.5 times heavier than native ground water. When TCE is present as an organic (hydrophobic) phase, it will displace water and sink as it dissolves. Vertical movement of a hydrophobic phase would be impeded by low-permeability sediments such as clay layers. Although density-induced movement may have been significant in the early stages of the contaminant entry in the aquifer system, no evidence for the presence of a hydrophobic phase of TCE has been found to date at Roosevelt Field, and the movement of VOC's is probably controlled mainly by hydraulic gradients of natural flow patterns and from pumping.

Biodegradation

Recently, Parsons and others (1984) and Kleopfer and others (1985) have demonstrated the dechlorination of TCE by bacteria under anaerobic conditions.

The primary dechlorination product was *cis*-1,2-dichloroethylene. This isomer was commonly detected in ground water containing TCE contamination at Roosevelt Field, which indicates the possible microbial metabolism of TCE. Parsons and others (1984) and Kleopfer and others (1985) also suggest that dichloroethylene is dechlorinated to form vinyl chloride; analysis of contaminated ground water at Roosevelt Field, however, did not include vinyl chloride.

Adsorption

Physical adsorption of organic contaminants to clastic and organic particles depends on the physical-chemical interaction of the compounds and the aquifer media. The adsorption of nonpolar organic solutes to sediment particles and particle coatings is directly proportional to the organic carbon content of the adsorbing media (Karickhoff and others, 1979; Schwarzenbach and Westall, 1981). Chiou and others (1979), who prefer to view the uptake of

Table 5.--Total organic carbon in core samples from well N10042 at Mitchel Field in central Nassau County, New York.

Depth (feet)	Percent organic carbon	Lithologic description
		Magothy aquifer
144	0.52	Sand, gray, fine to medium, clayey.
154	.59	Sand, gray, fine to medium, silty.
164	.04	Sand, brown, fine to coarse, silty.
174	19.	Clay, black, lignitic, slightly silty.
184	2.3	Clay, gray, lignitic, silty.
194	2.3	Clay, black, lignitic, micaceous.
204	.61	Sand, gray, fine to medium, silty.
214	4.1	Sand, gray, fine to medium, lignitic.
224	17.	Lignite, black, clayey.
234	.20	Sand, gray, fine to coarse, micaceous.
244	4.3	Clay, gray, slightly lignitic, silty.
264	.04	Sand, orange, fine to coarse, silty.
274	.13	Sand, brown-gray, fine to medium.
284	.06	Sand, gray, fine to medium, silty, micaceous.
294	.04	Sand, brown-gray, fine to coarse.
394	2.0	Sand, gray, medium to coarse, lignitic.
464	.03	Sand, brown, fine to medium.
524	<.01	Sand, brown, coarse; gravel, granule to pebble.
		Raritan confining unit
624	.51	Clay, gray, silty.
644	.06	Sand, gray, fine to medium, slightly clayey.
664	19.	Lignite, black; clay, gray, silty.
671	17.	Lignite, black; clay, gray, silty.

organic solutes by the medium as a reversible equilibrium-partitioning process rather than an adsorption process, have shown that isotherms for chlorinated organic solutes such as TCE are essentially linear and that their slopes are inversely proportional to each compound's solubility. Nonpolar organic solutes such as TCE, which have moderately low solubility in water, tend to adsorb readily to organic material in the aquifers. Sorptive effects of the inorganic fraction of aquifer material, such as clay minerals, seem to be negligible when the organic fraction exceeds 1 percent (Karickhoff and others, 1979). In aquifers that are deficient in organic carbon, such as the upper glacial aquifer, TCE's high mobility is therefore probably due in part to the low adsorptive capability of the medium.

The content of organic carbon in aquifer material at one well in the Roosevelt Field area is reported in table 5. Samples from the Magothy aquifer at well N10042 were taken from split-spoon cores 2 mi southeast of Roosevelt Field and analyzed for total organic carbon by the U.S. Geological Survey National Water-Quality Laboratory in Doraville, Ga. In general, sandy zones contain little organic carbon, whereas clay zones with abundant lignite may contain up to 23 percent organic carbon. These lignitic clay zones in the Magothy aquifer are laterally discontinuous and generally transmit water very slowly. The more permeable sandy zones, which transmit more water, may contain less than 1 percent organic carbon. Thus, the zones through which water moves most rapidly probably do not have the capacity to significantly attenuate organic solute transport by adsorption, which helps explain the continuing presence of TCE at lower depths in the Magothy aquifer.

SUMMARY AND CONCLUSIONS

In 1982, the U.S. Geological Survey began a study in cooperation with Nassau County to evaluate the occurrence and movement of chlorinated volatile organic compounds (VOC's) in ground water at Roosevelt Field, an area in central Nassau County where five public-supply wells have been affected by trichloroethylene (TCE) contamination. Of five public-supply wells and seven cooling-water supply wells at Roosevelt Field, six have yielded water that contains TCE in excess of New York State drinking-water guidelines. One cooling-water well that taps the Magothy aquifer has yielded water that contains 38,000 µg/L of TCE. The area was once an active commercial airfield but is now a large shopping mall and office-building complex. The source of the contamination has not been identified.

The aquifer system in central Nassau County consists of unconsolidated Pleistocene and Cretaceous deposits of gravel, sand, silt, and clay. The upper glacial aquifer, which contains the water table, overlies the Magothy aquifer and is in direct hydraulic contact with it. The upper glacial aquifer consists of 20 to 40 ft of saturated Pleistocene sand and gravel. Depth to water ranges from 25 to 50 ft. The Magothy aquifer, which overlies the Raritan confining unit, consists of alternating sequences and gradations of sand, silt, clay, and lignite, with gravel in the basal section. The Magothy

aquifer is about 500 ft thick at Roosevelt Field; the lower 150 ft provides most of the public-water supply. The Raritan confining unit and the Lloyd aquifer beneath form the base of the aquifer system, but no hydrologic or water-quality data are available from the Roosevelt Field area.

The regional movement of ground water in the upper glacial aquifer is south-southwestward from the mid-island ground-water divide, about 2 mi north of Roosevelt Field, to discharge areas near and beyond the south shore in southeastern Queens County and southwestern Nassau County. The regional water-table gradient at Roosevelt Field averages about 0.0012, and the average rate of horizontal movement is about 1 ft/d. Flow rates in the Magothy aquifer, which is much finer grained and has a lower mean hydraulic conductivity, range from negligible to 0.6 ft/d. The downward component of flow in the Magothy aquifer under natural conditions may range from 1/30 to 1/60 of the horizontal flow. Ground-water withdrawals from middle and basal sections of the Magothy aquifer induce higher rates of downward flow, especially during periods of peak demand for water supply in the summer.

During 1982-84, four public-supply wells at Roosevelt Field pumped more than 4 Mgal/d during peak water demand in the summer, and seven wells for cooling water pumped an additional 4 Mgal/d during warm weather. Water from the cooling-water wells was discharged to the upper glacial aquifer after use at two locations during the summer cooling season, typically from May to September. One location was the 2.5-acre Pembrook recharge basin, excavated in sand and gravel in southwestern Roosevelt Field, to which about 2 Mgal/d of wastewater from four cooling-water wells was discharged. The discharge water contained TCE, *cis*-1,2-dichloroethylene (DCE), and tetrachloroethylene (PCE), which was pumped from the Magothy aquifer. The second discharge location was a subsurface drain field at the Garden City Plaza office-building complex, to which about 2 Mgal/d of wastewater from two cooling-water wells was discharged. This wastewater also contained TCE and DCE and was pumped from the Magothy aquifer, but the water was partially treated by aeration stripping before it was discharged.

Water-table mounds form beneath both discharge sites during the summer cooling season. In 1982-84, the mound beneath Pembrook recharge basin persisted throughout the year because the basin also received storm runoff, but then rose to 3 to 4 ft above the regional water-table during the summer-discharge period. In August 1984, the discharge to the basin contained 13 lb/d of TCE and 3.2 lb/d of PCE. The mound beneath the Garden City Plaza drain field also was observed from May through September 1984, when it was 4 to 5 ft higher than the regional water table. Although the discharge was treated by aeration to remove VOC's, the treatment was only about 44 percent effective in August 1984. At that time, the treated discharge contained 9.6 lb/d of TCE and 1.3 lb/d of DCE.

Ground water was sampled for VOC's and common inorganic chemical constituents in public-supply wells, cooling-water supply wells, and monitoring wells during the summer of 1983 and the spring of 1984. In 1984, TCE was detected in 44 of 105 wells, and concentrations ranged from less than the detection limit (1 µg/L) to 38,000 µg/L. Concentrations of DCE ranged from less than detection limit to 2,800 µg/L, and PCE concentrations ranged from less than detection limit to 350 µg/L.

Three plumes of trichloroethylene contamination have been delineated at Roosevelt Field, two of which are formed by the seasonal discharge of contaminated cooling water and overlie the original plume, which is in the upper glacial and Magothy aquifers. One plume originated at the drain field; the other originated at the Pembrook recharge basin, 1,000 ft downgradient of the drain field. Contaminated water moved radially from each cooling-water discharge center, where local flow rates may have exceeded 10 ft/d. The two plumes have merged in southwestern Roosevelt Field and extend more than 1,000 ft to the south-southwest along the axis of regional flow in the upper glacial aquifer. The concentrations of inorganic chemical constituents in the two discharge plumes are similar to those in ambient ground water. The two plumes differ, however, in that the discharge from Pembrook recharge basin contains TCE, PCE, and DCE, whereas the discharge from the drain field contains only TCE and DCE.

Discharge of contaminated cooling water ceased during the winter, and the inflow of uncontaminated storm runoff to the recharge basin dispersed the ground water contaminated by the preceding summer's discharge. Ground-water quality and temperature in monitoring wells around the basin fluctuated seasonally and reflect the quality and temperature of water that is discharged to the basin. Concentrations of TCE at one monitoring well (N10097) at the edge of the basin seasonally ranged from 3 to 300 µg/L, and temperature ranged from 7.3°C to 22.6°C. The magnitude of fluctuation in TCE concentration and temperature decreases with distance from the basin, and no seasonal variations were detected at monitoring wells 1,000 ft downgradient.

Although the Magothy aquifer is 10 to 15 times thicker than the upper glacial aquifer, the number of wells that tap it at Roosevelt Field is small; thus, the distribution of TCE and DCE in the Magothy is less accurately delineated than in the upper glacial aquifer. Concentrations of TCE exceeded 38,000 µg/L in 1984 in a cooling-water well (N8050) screened 300 ft deep, directly north of Garden City Plaza, and were 170 µg/L in an adjacent public-supply well (N5486) screened at 450 ft when the well was abandoned and destroyed in 1980. Four other public-supply wells, all screened below 400 ft, have TCE concentrations that are detectable but less than 50 µg/L. Tetrachloroethylene was detected in only one cooling-supply well (N5507) and indicates a separate source of VOC contamination. The two cooling-water wells (N5507 and N8050) that contributed contaminated discharge to Pembrook recharge basin were both abandoned in 1985, thereby stopping the inflow of contaminants to the basin.

The contaminated zone in the Magothy aquifer contains high concentrations of TCE and DCE associated with the unknown source of contamination; the plume is elongated and diffused south-southwestward along regional flow lines. Regional flow rates in the Magothy aquifer are less than 1/3 the flow rates in the upper glacial aquifer, and the plume area is proportionately much smaller. At Roosevelt Field, the heterogeneity and anisotropy of the Magothy aquifer, combined with the effects of increased vertical hydraulic gradients from ground-water withdrawals, create a highly variable velocity distribution. In addition, increased pumping for cooling-water supplies during warm weather increases hydraulic gradients near each pumping center. A sandy vertical zone that lacks clay layers provides good vertical hydraulic connection in the aquifer system in the area of a possible contaminant source near abandoned

public-supply well N5486. Pumping from middle and basal sections of the Magothy aquifer in this area has increased the rates of downward contaminant advection, especially during summer, when pumpage has exceeded 6 Mgal/d. This advection has been cumulative through time and has transported TCE and associated contaminants as deeply as the basal section of the aquifer, 500 ft below land surface. Thus, the combined effects of horizontal flow along the regional hydraulic gradient, which controls the regional flow of ground water when pumping is at a minimum during cool weather, and increased downward flow induced by pumping during warm weather have moved and dispersed the VOC contaminants in the aquifer system. This movement and dispersion has caused TCE and DCE to reach the base of the Magothy aquifer at Roosevelt Field in less than 40 years of transit, which indicates that natural flow patterns in this area have been significantly altered by pumping.

REFERENCES CITED

Anderson, M. P., 1984, Movement of contaminants in groundwater--groundwater transport-advection and dispersion, in Studies in geophysics, groundwater contamination: National Academy Press, p. 37-45.

Cherry, J. A., Gillham, R. W., and Barker, J. F., 1984, Contaminants in groundwater--chemical processes, in Studies in geophysics, groundwater contamination: National Academy Press, p. 46-64.

Chiou, C. T., Peters, L. J., and Freed, V. H., 1979, A physical concept of soil-water equilibria for nonionic organic compounds: Science, v. 206, p. 831-832.

Cohen, Philip, Franke, O. L., and Foxworthy, B. L., 1968, An atlas of Long Island's water resources: New York State Water Resources Commission Bulletin 62, 117 p.

Dilling, W. L., Tefertiller, N. B., and Kallos, G. J., 1975, Evaporation rates and reactivities of methylene chloride, chloroform, 1,1,1-trichloroethane, trichloroethylene, tetrachloroethylene, and other chlorinated compounds in dilute aqueous solutions: Environmental Science and Technology, v. 9, no. 9, p. 833-838.

Donaldson, C. D., and Koszalka, E. J., 1983a, Potentiometric surface of the Magothy aquifer, Long Island, New York, in March 1979: U.S. Geological Survey Open-File Report 82-160, 2 sheets, scale 1:125,000.

_____ 1983b, Potentiometric surface of the Lloyd aquifer, Long Island, in January 1979: U.S. Geological Survey Open-File Report 82-162, 2 sheets, scale 1:125,000.

_____ 1983c, Water table on Long Island, New York, March 1979: U.S. Geological Survey Open-File Report 82-163, 2 sheets, scale 1:125,000.

Franke, O. L., and Cohen, Philip, 1972, Regional rates of ground-water movement on Long Island, New York: U.S. Geological Survey Professional Paper 800-C, p. C271-277.

REFERENCES CITED (Continued)

Franke, O. L., and McClymonds, N. E., 1972, Summary of the hydrologic situation on Long Island, New York, as a guide to water-management alternatives: U.S. Geological Survey Professional Paper 627-F, 59 p.

Getzen, R. T., 1977, Analog-model analysis of regional three-dimensional flow in the ground-water reservoir of Long Island, New York: U.S. Geological Survey Professional Paper 982, 49 p.

Isbister, John, 1966, Geology and hydrology of northeastern Nassau County, Long Island, New York: U.S. Geological Survey Water-Supply Paper 1825, 89 p.

Karickhoff, S. W., Brown, D. S., and Scott, T. A., 1979, Sorption of hydrophobic pollutants on natural sediments: Water Research, v. 13, no. 3, p. 241-248.

Katz, B. G., and Lindner, J. B., 1978, Nitrogen concentration in Nassau County ground water from early 1950's through 1976 [abstract]: Adelphi, N.Y., American Chemical Society Conference, April 23, 1978, 1 p.

Kilburn, Chabot, 1979, Hydrogeology of the Town of North Hempstead, Nassau County, Long Island, New York: Long Island Water Resources Bulletin 12, 87 p.

Kilburn, Chabot, and Krulikas, R. K., 1987, Hydrogeology and ground-water quality of the northern part of the Town of Oyster Bay, Nassau County, New York, in 1980: U.S. Geological Survey Open-File Report 85-4051, 61 p.

Kleopfer, R. D., Easley, D. M., Haas, B. B., Diehl, T. G., Jackson, D. E., and Wurrey, C. J., 1985, Anaerobic degradation of trichloroethylene in soil: Environmental Science and Technology, v. 19, no. 3, p. 277-280.

Lindner, J. B., and Reilly, T. E., 1983, Analysis of three tests of the unconfined aquifer in southern Nassau County, Long Island, New York: U.S. Geological Survey Water-Resources Investigations Report 82-4021, 52 p.

Mackay, S. L., Fleisher, M. B., and Cusumano, R. D., 1979, Inventory for "Report on survey of consumer products containing or suspected of containing harmful organic chemicals and having the potential of contaminating the ground water of Nassau County, New York: Nassau County Department of Health, 17 p.

McCarty, P. L, Reinhard, M., and Rittmann, B. E., 1981, Trace organics in ground water: Environmental Science and Technology, v. 15, no. 1, p. 40-51.

McClymonds, N. E., and Franke, O. L., 1972, Water-transmitting properties of aquifers on Long Island, New York: U.S. Geological Survey Professional Paper 627-E, 24 p.

REFERENCES CITED (Continued)

Miller, J. F., and Frederick, R. H., 1969, The precipitation regime of Long Island, New York: U.S. Geological Survey Professional Paper 627-A, 21 p.

Myott, D. H., 1980, Groundwater quality assessment, Nassau County, New York, 1978 report year: Nassau County Department of Health, 39 p.

Narang, R. S., and Bush, D., 1980, Determination of arenes, vinyl chloride, and other volatile haloorganic compounds in water at microgram-per-liter levels by gas chromatography: Analytical Chemistry, v. 52, no. 13, p. 2076-2079.

National Academy of Sciences, 1977, Drinking water and health: National Research Council, Washington, D.C., 939 p.

Parsons, Frances, Wood, P. R., and DeMarco, Jack, 1984, Transformations of tetrachloroethene and trichloroethene in microcosms and groundwater: Journal of American Water Works Association, v. 76, no. 2, p. 56-59.

Pearsall, K. A., and Eckhardt, D. A., 1987, Effects of selected sampling equipment and procedures on the concentrations of trichloroethylene and related compounds in ground-water samples: Ground Water Monitoring Review, v. 7, no. 2, p. 64-73.

Perlmutter, N. M., and Geraghty, J. J., 1963, Geology and ground-water conditions in southern Nassau and southeastern Queens Counties, Long Island, New York: U.S. Geological Survey Water-Supply Paper 1613-A, 205 p.

Philips, K. J., and Gelhar, L. W., 1978, Contaminant transport to deep wells: American Society of Civil Engineers Journal of the Hydraulics Division, proceedings, v. 104, no. HY6, p. 807-819.

Reilly, T. E., 1978, Convective contaminant transport to pumping well: American Society of Civil Engineers Journal of the Hydraulics Division proceedings, v. 104, no. HY12, p. 1565-1575.

Roberts, P. V., Reinhard, M., and Valocchi, A. J., 1982, Movement of organic contaminants in ground water--implications for water supply: Journal of American Water Works Association, v. 74, no. 8, p. 408-413.

Schwarzenbach, R. P., and Westall, John, 1981, Transport of nonpolar organic compounds from surface water to ground water--laboratory sorption studies: Environmental Science and Technology, v. 15, no. 11, p. 1360-1367.

Skougstad, M. W., Fishman, M. J., Friedman, L. C. Erdmann, D. E. and Duncan, S. S., eds., 1979, Methods for determination of inorganic substances in water and fluvial sediments: Techniques of Water-Resources Investigations of the U. S. Geological Survey, Book 5, Laboratory Analysis, Chapter A1, 626 p.

REFERENCES CITED (continued)

Swarzenski, W. V., 1963, Hydrogeology of northwestern Nassau and northeastern Queens Counties, Long Island, New York: U.S. Geological Survey Water-Supply Paper 1657, 90 p.

U.S. Environmental Protection Agency, 1979a, Methods for chemical analysis of water and wastes: Cincinnati, Ohio, Environmental Monitoring and Support Laboratory, Office of Research and Development, U.S. Environmental Protection Agency Publication EPA-600/4-79-020, 460 p.

_____ 1979b, Water-related environmental fate of 129 priority pollutants--volume II: Washington, D.C., Office of Water Planning and Standards, U.S. Environmental Protection Agency Publication EPA-440/4-79-029b, p. 52:1-52:13.

U.S. Environmental Protection Agency, 1979c, Status assessment of toxic chemicals--Trichloroethylene: Cincinnati, Ohio, Industrial and Environmental Research Laboratory, Office of Research and Development, U.S. Environmental Protection Agency Publication EPA-600/2-79-210m, 25 p.

Wershaw, R.L., Fishman, M. J. Grabbe, R. R. and Lowe, L. E. 1982, Methods for analysis of organic substances in water: U.S. Geological Survey Open-File Report 82-1004, 180 p.

Table 6.--Data on wells in the Roosevelt Field area, Nassau County, New York

Well	Latitude ° ' "	Longitude ° ' "	Owner	Depth to screen, in feet below land surface: Top (feet)	Bottom (feet)	Diameter (inches)
79	404252	733714	Village of Hempstead	338	428	10
80	404256	733712	Village of Hempstead	428	478	16
81	404305	733709	Village of Hempstead	360	420	28
82	404308	733707	Village of Hempstead	390	542	--
83	404306	733713	Village of Hempstead	363	403	28
94	404350	733825	Village of Garden City	322	372	18
95	404352	733830	Village of Garden City	474	534	20
97	404448	733812	Village of Garden City	310	369	16
101	404521	733534	Village of Westbury	280	340	18
1139	404415	733803	Nassau County	65	68	2
1141	404304	733752	Nassau County	40	43	1
1160	404359	733616	Nassau County	53	58	4
1180	404411	733437	Nassau County	30	32	1
1451	404355	733711	Nassau County	32	35	1
1697	404357	733837	Village of Garden City	478	518	24
2418	404403	733631	Unknown	40	55	10
2419	404402	733636	Unknown	37	58	12
2747	404446	733650	Village of Carle Place	278	328	18
2748	404445	733651	Village of Carle Place	460	510	16
3185	404416	733847	Village of Mineola	423	463	10
3699	404446	733713	Destroyed	67	89	10
3700	404448	733705	Destroyed	52	73	10
3890	404455	733700	Unknown	22	33	6
3934	404402	733708	Village of Garden City	377	417	18
3935	404400	733705	Village of Garden City	370	410	18
4082	404525	733732	Village of Mineola	422	462	18
4206	404524	733632	Village of Carle Place	305	355	18
4425	404259	733715	Village of Hempstead	325	365	20
4772	404437	733743	Destroyed	197	237	6
5484	404420	733644	Town of Hempstead	500	572	20
5485	404423	733655	Town of Hempstead	473	554	20
5486	404415	733655	Town of Hempstead	450	556	20
5507	404413	733647	R.H. Macy and Company	107	330	16
5596	404454	733726	Village of Mineola	403	463	18
5654	404451	722526	Village of WEstbury	275	335	20
5725	404348	733649	Newsday, Inc.	46	56	10
6045	404432	733656	Town of Hempstead	277	328	16
6046	404416	733548	Town of Hempstead	145	175	10
6315	404526	733626	Village of Carle Place	298	348	12
6512	404428	733636	Island Heliport, Inc.	61	71	6
6545	404426	733636	Island Heliport, Inc.	30	40	6
6841	404438	733610	Island Inn	312	337	8
6842	404442	733610	Island Inn	143	158	6
6949	404351	733648	Newsday, Inc.	41	46	6
6951	404439	733614	Avis International, Inc.	304	334	12

Table 6.--Data on wells in the Roosevelt Field area, Nassau County, New York (cont.)

Well	Latitude ° ′ ″	Longitude ° ′ ″	Owner	Depth to screen, in feet below land surface: Top (feet)	Bottom (feet)	Diameter (inches)
6994	404418	733617	Georgian-Web Press, Inc.	250	270	8
6998	404438	733607	Island Inn	39	60	6
7174	404317	733632	M.C.M. Beverage Company	57	67	20
7298	404303	733714	Village of Hempstead	394	444	20
7500	404419	733450	Nassau County	405	458	20
7785	404526	733534	Village of Westbury	330	400	20
7957	404420	733531	Town of Hempstead	433	519	20
8007	404543	733549	Village of Westbury	490	564	20
8050	404422	733700	Bernhardt and Stein, Inc.	300	328	8
8068	404357	733646	VMI, Inc.	265	291	10
8305	404453	733713	BOCES	51	60	8
8457	404457	733607	Village of Carle Place	355	435	20
8458	404422	733644	Pembrook Management, Inc.	290	350	12
8474	404325	733630	Town of Hempstead	485	556	20
8475	404325	733630	Town of Hempstead	409	481	20
8576	404453	733834	Village of Mineola	445	505	12
8598	404239	733555	Nassau County	42	45	1
8666	404418	733702	VMI, Inc.	43	67	8
8682	404440	733529	Uman Parante Company	89	94	8
8753	404440	733529	Uman Parante Company	100	110	8
8958	404306	733537	Nassau County	30	35	2
8971	404344	733543	Nassau County	30	35	1
8984	404452	733446	Nassau County	43	48	4
9057	404242	733422	Nassau County	42	47	4
9078	404324	733422	Nassau County	60	65	4
9201	404327	733359	Nassau County	40	45	6
9222	404351	733327	Nassau County	40	45	6
9225	404331	733308	Nassau County	39	44	6
9234	404430	733310	Nassau County	200	205	6
9236	404430	733310	Nassau County	45	50	6
9239	404410	733332	Nassau County	200	205	6
9241	404410	733332	Nassau County	40	45	6
9310	404410	733660	VMI, Inc.	180	230	12
9311	404418	733702	VMI, Inc.	189	229	12
9355	404337	733605	Nassau County	58	63	4
9398	404311	733716	Nassau County	21	22	2
9521	404411	733610	Town of Hempstead	475	601	20
9703	404356	733618	Nassau County	96	106	4
9709	404416	733521	Town of Hempstead	305	363	16
9713	404356	733618	Nassau County	205	215	4
9751	404416	733521	Town of Hempstead	125	286	16
9802	404330	733530	Nassau County	132	142	4
9803	404330	733530	Nassau County	54	59	4
9804	404336	733509	Nassau County	130	140	4
9805	404336	733509	Nassau County	53	58	4

Table 6.--Data on wells in the Roosevelt Field area, Nassau County, New York (cont.)

Well	Latitude ° ′ ″	Longitude ° ′ ″	Owner	Depth to screen, in feet below land surface: Top (feet)	Bottom (feet)	Diameter (inches)
9846	404412	733510	Town of Hempstead	500	600	14
9914	404409	733741	Nassau County	49	54	4
9938	404526	733335	Nassau County	72	77	4
9939	404435	733343	Nassau County	66	71	4
9940	404523	733634	Nassau County	45	50	4
9941	404443	733625	Nassau County	42	47	4
9942	404455	733814	Nassau County	61	66	4
9943	404342	733805	Nassau County	61	66	4
9950	404513	733534	Nassau County	64	69	4
9951	404431	733703	Nassau County	38	54	4
9952	404427	733704	Nassau County	48	54	4
9953	404421	733705	Nassau County	48	54	4
9954	404407	733704	Nassau County	48	54	4
9955	404406	733657	Nassau County	48	54	4
9956	404420	733644	Nassau County	48	54	4
9957	404423	733654	Nassau County	48	54	4
9958	404416	733654	Nassau County	48	54	4
9959	404412	733634	Nassau County	48	54	4
9960	404423	733639	Nassau County	48	54	4
9961	404423	733643	Nassau County	48	54	4
9962	404446	733724	Nassau County	48	54	4
9963	404446	733650	Nassau County	48	54	4
9964	404403	733706	Nassau County	48	54	4
9965	404413	733707	Nassau County	48	54	4
9966	404358	733656	Nassau County	48	54	4
9967	404404	733631	Nassau County	48	54	4
9968	404432	733712	Nassau County	62	68	4
9971	404417	733705	VMI, Inc.	35	40	1
9972	404416	733705	VMI, Inc.	35	40	1
9973	404415	733705	VMI, Inc.	35	40	1
9974	404410	733701	VMI, Inc.	30	35	1
10019	404407	733704	Nassau County	223	228	4
10020	404406	733657	Nassau County	185	190	4
10033	404259	733806	Village of Garden City	440	540	20
10034	404258	733806	Village of Garden City	509	570	20
10035	404338	733715	Nassau County	48	53	4
10041	404336	733509	Nassau County	0	0	18
10042	404330	733530	Nassau County	0	0	18
10043	404419	733616	Georgian-Web Press, Inc.	165	185	8
10076	404438	733610	Island Inn	207	334	10
10094	404416	733720	Nassau County	60	65	4
10095	404417	733711	U.S. Geological Survey	48	51	2
10096	404403	733660	U.S. Geological Survey	35	36	2
10097	404359	733702	U.S. Geological Survey	35	36	2
10202	404348	733724	U.S. Geological Survey	42	45	2
10204	404352	733656	U.S. Geological Survey	41	44	2
10205	404308	733706	U.S. Geological Survey	41	44	2

Table 7.--Concentrations of volatile organic compounds in ground-water samples collected by Nassau County before 1983.

[Analyses by Nassau County Department of Health except where noted. All concentrations are in micrograms per liter.]

Well number	Aquifer[1]	Sampling Date (mo/day/yr)	1,2-Dichloro-ethylene	Trichloro-ethylene	Tetrachloro-ethylene	Total VOCs[2]
1160	G	060280	--	7	2	13
		100180	<30	6	1	9
		022582	<25	3	--	26
		072682	<7	1	24	27
		120182	1	1	35	39
2747	M	120377	--	<4	<2	e
		123077	--	<4	<2	e
		101783P	<1	<1	<1	7
		102083P	<1	2	<1	160
2748	M	091180	<1	<1	<1	e
		080481	--	<4	<2	e
		090381	<1	<1	<1	e
		012782	<25	3	<1	3
3699	M	070279	--	4	2	13
		061780	--	4	2	15
		061681	<5	4	4	74
		051282	<25	5	2	56
3700	M	051282	<25	3	2	13
3934	M	100680	<30	11	4	20
		092380	<1	12	2	16
		051381	--	5	2	9
		101381	<1	8	2	14
		031682	--	6	2	14
3935	M	091179	--	12	1	27
		082980	--	11	2	17
		100680	<30	14	5	24
		091581	--	14	5	24
5484	M	092377	--	<4	<2	e
		022378	--	<1	<1	e
		101978	--	<1	<1	e
		081679	--	<5	<5	e
		091379	--	<5	<5	e
		022780	--	3	<3	3
		022780	--	4	<2	4
		022780	--	4	<2	4
		022980	--	3	<3	3
		061380	--	4	<3	4
		071580	--	6	<2	6
		071880	--	4	<2	4
		021781	--	12	1	21
		050481	--	7	<1	7

1 G = upper glacial aquifer; M = Magothy aquifer
2 e All VOCs below detection limits

Table 7.--Concentrations of volatile organic compounds in ground-water samples collected by Nassau County before 1989 (cont.)

Well number	Aquifer[1]	Sampling Date (mo/day/yr)	1,2-Dichloro-ethylene	Trichloro-ethylene	Tetrachloro-ethylene	Total VOCs
5484 (cont.)	M	052181	--	16	1	21
		052681	--	7	<2	7
		061981	--	6	<1	9
		021782	--	1	<1	1
5485	M	092377	--	<4	<2	e
		012678	--	24	<2	24
		022378	--	43	<1	43
		031578	--	32	<2	32
		101378	--	21	<1	24
		110678	--	43	<1	43
		120878	--	39	<2	39
		081679	--	60	<5	60
		082979	--	85	<2	85
		082979	--	100	<5	100
		091079	--	48	<3	48
		091379	--	85	<2	85
		022780	--	46	<3	46
		022780	--	57	<3	57
		022780	--	57	<3	61
		022780	--	36	<2	36
		022780	--	37	<2	37
		062480	--	24	<3	24
		062580	--	25	<3	25
		062680	--	33	<3	33
		070380	--	24	<2	24
		071480	--	14	<3	14
		072980	--	13	<3	13
		073080	--	19	<2	19
		073080	--	15	<3	15
		073180	--	27	<3	31
		080180	--	21	<3	21
		080480	--	36	no sample	36
		080580	--	32	<3	32
		080780	--	37	<3	37
		081180	--	48	<3	48
		081180	--	30	<3	30
		081280	--	35	<3	35
		081480	--	38	<3	38
		081880	--	42	<3	42
		082180	--	42	<3	42
		082580	--	46	<3	46
		082580	--	40	<3	40
		082780	--	53	<2	53
		090280	--	54	<3	54
		090380	--	44	<3	44
		052181	--	20	2	25
		061981	--	2	<1	6
		062281	--	11	<1	15
		063081	--	10	<1	10
		070881	--	13	<1	14
		072081	--	18	<1	18
		072781	--	24	<1	24

Table 7.--Concentrations of volatile organic compounds in ground-water samples collected by Nassau County before 1983 (cont.)

Well number	Aquifer[1]	Sampling Date (mo/day/yr)	1,2-Dichloro-ethylene	Trichloro-ethylene	Tetrachloro-ethylene	Total VOC's
5485 (cont.)	M	080481	--	28	<1	28
		081081	--	16	<1	16
		081781	--	29	<1	31
		091081	--	7	<1	10
		092181	--	29	<1	31
		100681	--	19	<1	21
		111981	--	19	<1	22
		020382	--	19	1	20
		022582	--	12	<1	15
		031182	--	17	<1	19
		043082	--	11	<1	14
		061882	--	11	<1	13
		072682	--	13	<1	13
		082082	--	6	<1	6
		092382	--	13	<1	13
		102082	--	24	<1	26
5486	M	092377	--	12	8	20
		012678	--	15	8	32
		031578	--	24	6	46
		033078	--	32	17	70
		101378	--	88	8	113
		101878	--	99	10	127
		120878	--	39	<2	39
		042979	--	40	15	96
		081779	--	40	15	80
		082979	--	76	7	96
		082979	--	64	12	102
		091079	--	41	15	103
		091279	--	41	15	97
		022980	--	70	<3	102
		022980	--	68	<3	97
		022980	--	72	<3	104
		022980	--	170	3	200
		022980	--	150	3	170
5507	M	101079	--	240	160	460
		072880	--	300	190	590
		062381	<25	250	210	490
		051882	<25	360	240	630
		062083	<4	50	6	58
5596	M	121879	--	<4	<2	e
		101080	--	<4	<2	e
		020981	--	<4	<2	e
		050682	--	<1	<1	e
5725	G	070782	<7	32	5	38

1 G = upper glacial aquifer; M = Magothy aquifer
2 e All VOCs below detection limits

Table 7.--Concentrations of volatile organic compounds in ground-water samples collected by Nassau County before 1988 (cont.)

Well number	Aquifer[1]	Sampling Date (mo/day/yr)	1,2-Dichloro-ethylene	Trichloro-ethylene	Tetrachloro-ethylene	Total VOC's
6045	M	102379	--	4	2	6
		072880	--	<4	3	3
		062481	<25	4	4	8
		051982	<25	4	3	9
6841	M	112179	--	<4	<2	e
		072880	--	<4	<2	e
		062981	<25	<1	1	1
		052582	<25	<1	<1	1
6842	M	112979	--	<4	2	32
		072880	--	<4	<2	27
		062381	<25	1	<1	22
		052582	<25	2	<1	20
6949	G	070782	<7	18	2	25
6994	M	101079	--	<4	<2	e
		072880	--	<4	<2	e
		062481	--	1	1	2
		051282	<25	<1	<1	e
7174	G	042478	--	3	3	7
		031379	--	<4	2	4
		120180	--	<1	<1	30
		011981	<5	1	1	3
8050	M	062381	975	3700	61	4800
		051882	1500	2400	54	4100
8068	M	072980	--	8	2	23
		093080	<30	9	2	220
		060282	<25	1	1	2
8305	G	060778	--	8	3	48
		071679	--	<4	<2	21
8457	M	122178	<1	2	1	3
		092779	<1	<1	<1	e
		091880	<1	<1	<1	e
		090381	<1	<1	<1	e
8458	M	101079	--	62	15	79
		072880	--	44	9	53
		062381	<25	43	19	65
		051282	<25	32	11	45
8474	M	080779	--	<5	<5	e
		031480	--	<3	<3	4
		052681	--	<4	<2	e
		060282	<25	1	<1	1

Table 7.--Concentrations of volatile organic compounds in ground-water samples collected by Nassau County before 1983 (cont.)

Well number	Aquifer[1]	Sampling Date (mo/day/yr)	1,2-Dichloro-ethylene	Trichloro-ethylene	Tetrachloro-ethylene	Total VOCs
8475	M	080779	--	<5	<5	e
		031480	--	<3	<3	e
		052681	--	<4	<2	e
		060282	<25	<1	<1	e
8666	G	031781	<5	120	1	120
8682	M	102379	--	<4	4	9
		100880	<30	1	2	48
		052582	<25	1	1	8
8753	M	100880	<30	2	2	75
		052582	<25	1	1	3
9310	M	120579	--	9	<2	46
		072880	--	29	2	63
		021781	<5	140	9	200
		080781P	<10	52	<2	74
		051882	<25	340	8	400
9311	M	120579	--	930	2	930
		072880	--	2200	6	2200
		021781	<5	400	1	400
		080781P	200	2000	12	2200
		051882	150	1300	3	1500
9355	G	091478	--	<4	<2	54
		060280	--	<4	<2	e
		100280	<30	1	4	22
		010782	<25	<1	<1	31
9521	M	120280	<1	<1	<1	e
		052681	--	<4	<2	e
		020382	--	<1	<1	e
		021782	--	<1	<1	e
9914	G	111682	<1	1	<1	1
9951	G	070182	<7	4	2	19
		111682	<1	1	<1	24
9952	G	063082	<7	14	1	35
		111882	<1	5	<1	6
9953	G	062882	<7	<1	<1	1
		111682	24	210	2	240
9954	G	061782	30	220	21	280
		111582	8	110	36	160
9955	G	061882	<7	36	21	58
		111782	79	510	71	670

1 G = upper glacial aquifer; M = Magothy aquifer
2 e all VOCs below detection limits

Table 7.--Concentrations of volatile organic compounds in ground-water samples collected by Nassau County before 1983 (cont.)

Well number	Aquifer[1]	Sampling Date (mo/day/yr)	1,2-Dichloro-ethylene	Trichloro-ethylene	Tetrachloro-ethylene	Total VOC's
9956	G	063082	<7	17	<1	18
		111782	<1	5	<1	6
9957	G	063082	<7	<1	1	1
		111782	<1	2	<1	2
9958	G	063082	<7	1	1	3
		111782	5	11	<1	18
9959	G	062982	<7	<1	1	3
		111582	<1	1	<1	2
9960	G	062882	7	33	1	42
		111582	1	27	1	29
9961	G	062982	<7	1	1	3
		111582	<1	<1	1	2
9962	G	070882	<7	<1	<1	1
		111682	<1	<1	<1	21
9963	G	070182	<7	10	4	26
		111682	<1	7	4	20
9964	G	061882	<7	30	11	42
		062482	16	120	24	160
		111782	45	360	68	480
9965	G	070882	<7	3	<1	3
		063082	<7	3	1	5
9966	G	062482	13	100	14	130
9967	G	062882	<7	<1	1	2
		111582	<1	<1	<1	1
9968	G	111682	<1	1	9	20
		120682	<1	<1	4	5
9971	G	081381P	<5	10	<1	87
9972	G	081381P	<5	15	<1	64
9973	G	081381P	<5	<1	<1	e
9974	G	081381P	<5	50	2	70
10019	M	111582	1	19	9	32

Table 8.--Concentrations of volatile organic compounds in ground-water samples collected by U.S. Geological Survey 1983-84

[Analyses by Nassau County Department of Health, except where noted. All concentrations are in micrograms per liter.]

A. WELLS

Well number	Aquifer[1]	Sampling Date (mo,day,yr)[2]	1,2-Dichloro-ethylene	Trichloro-ethylene	Tetrachloro-ethylene	Total VOCs[3]
79	M	011184	<4	<1	<1	e
		040284	<4	<3	<1	e
80	M	011184	<4	<1	<1	e
81	M	111484	<15	<1	<1	e
82	M	011184	<4	<1	<1	e
83	M	040284	<4	29	15	44
95	M	070384	<5	<1	<1	e
97	M	060484	<5	<1	<1	e
		111384	<15	<1	<1	e
101	M	112684	<15	<1	6	6
1139	G	050884	<5	8	1	14
1141	G	050884	<5	<1	<1	e
1160	G	082583	<4	3	7	43
		082583N	<1	4	15	70
		041984	<4	<3	3	56
		041984N	<3	<3	3	92
1451	G	050384	<4	<3	<1	e
1697	M	070284	<5	<1	<1	e
2748	M	080383	<4	<1	<1	e
		041184	<4	<3	<1	e
3185	M	051084	<5	3	4	13
3699	M	080983	<4	2	5	19
		050184	<4	<3	2	10
3700	M	082283	<4	4	2	14
		041884	<4	<3	2	6
3934	M	082483	<4	9	1	13
		041384	<4	17	2	22

1 G = upper glacial aquifer; M = Magothy aquifer
2 Analyses from same well on same date are of duplicate samples
N = analysis by National Water Quality Laboratory, Atlanta, Ga.
3 e = all volatile organic compounds below detection limits

Table 8.--Concentrations of volatile organic compounds in ground-water samples collected by U.S. Geological Survey 1983-84 (cont.)

A. WELLS (continued)

Well number	Aquifer[1]	Sampling Date (mo,day,yr)[2]	1,2-Dichloro-ethylene	Trichloro-ethylene	Tetrachloro-ethylene	Total VOCs[3]
3935	M	082483	<4	15	2	24
		041184	<4	18	3	27
4082	M	060484	<5	<1	<1	1
		120784	<15	<1	<1	e
4206	M	060484	<5	<1	<1	e
4425	M	111484	<15	19	8	27
4772	G	042084	<4	<3	<1	e
5484	M	081083	<4	8	<1	8
		040684	<4	11	1	13
5485	M	090783	5	--	1	6
		041284	<4	22	<1	26
5507	M	080383	10	260	170	470
		080383N	6	240	160	430
		041884	<4	440	140	600
		041884N	6	330	140	510
		080784	<4	380	350	840
5596	M	080383	<4	<1	<1	e
		041384	<4	<3	<1	e
5725	G	080383	7	49	7	65
		051184	3	140	14	170
6045	M	080983	<4	3	3	6
		080983N	3	7	<1	10
		042384	<4	5	4	9
		042384N	<3	5	3	8
		080784	<4	3	3	6
6315	M	041184	<4	<3	<1	e
6842	M	082283	<4	5	<1	32
		042384	<4	3	<1	9
6949	G	080383	11	51	7	7
		051184	<5	12	3	38
7298	M	111484	<15	<1	<1	e
7500	M	041284	<4	<3	<1	e
7785	M	112684	<15	<1	<1	e
7957	M	081083	<4	<1	<1	1
		041284	<4	<3	<1	e

Table 8.--Concentrations of volatile organic compounds in ground-water samples collected by U.S. Geological Survey 1983-84 (cont.)

A. WELLS (continued)

Well number	Aquifer[1]	Sampling Date (mo,day,yr)[2]	1,2-Dichloro-ethylene	Trichloro-ethylene	Tetrachloro-ethylene	Total VOCs[3]
8007	M	042384	<4	<3	<1	e
		082084	<5	<1	<1	e
8050	M	080483	720	2100	34	2900
		080483N	1400	13000	36	14000
		050284	2800	38000	87	41000
		050284N	2500	23000	77	26000
		080784	1100	13000	47	14000
8068	M	080983	8	14	4	42
		042384	4	15	3	27
8457	M	080383	<4	<1	<1	e
		041184	<4	<3	<1	e
8458	M	080983	9	51	19	84
		042684	<4	39	16	60
		080784	<4	37	2	64
8474	M	081083	<4	<1	<1	e
		041184	<4	<3	<1	e
8475	M	081083	<4	<1	<1	e
		040684	<4	<3	<1	e
8576	M	041384	<4	<3	2	2
8598	G	050784	<5	<1	<1	e
8666	G	080883	92	450	2	550
		080883N	140	580	7	740
		042484	84	540	2	630
8682	M	082483	<4	6	3	67
8753	M	082483	<4	5	1	29
		051084	<5	1	1	11
8958	G	050184	<4	<3	<1	2
		050184N	<3	<3	<3	e
8971	G	051484	<5	<1	<1	e
8984	G	051684	<5	<1	<1	4
9057	G	051784	<5	<1	<1	4
9078	G	051684	<5	<1	<1	6

1 G = upper glacial aquifer; M = Magothy aquifer
2 Analyses from same well on same date are of duplicate samples
N analysis by National Water Quality Laboratory, Atlanta, Ga.
3 e=all volatile organic compounds below detection limits

Table 8.--Concentrations of volatile organic compounds in ground-water samples collected by U.S. Geological Survey 1983-84 (cont.)

A. WELLS (continued)

Well number	Aquifer[1]	Sampling Date (mo,day,yr)[2]	1,2-Dichloro-ethylene	Trichloro-ethylene	Tetrachloro-ethylene	Total VOCs[3]
9310	M	080983	42	370	11	450
		042684	120	1300	12	1500
		042684N	160	950	9	1200
		080884	73	810	19	930
9311	M	080983	190	990	4	1200
		080983N	490	2800	10	3300
		041984	78	550	2	630
		041984N	97	450	<3	550
		080884	530	3000	10	3500
9355	G	043084	<4	<3	<1	3
		043084N	<3	<3	<3	e
9398	G	091984	no sample	<1	<1	e
9521	M	081083	<4	<1	<1	e
		040684	<4	<3	<1	e
9703	M	051484	260	18	36	520
9709	M	083083	<4	2	<1	2
		041784	<4	<3	<1	e
9713	M	051484	<5	<1	<1	e
9751	M	083083	<4	4	4	4
		050184	<4	<3	<1	e
9802	M	051584	<5	2	<1	35
9803	G	050284	<4	51	26	400
9804	M	051684	<5	<1	<1	e
9805	G	050284	<4	3	<1	4
9846	M	081083	<4	1	<1	1
		051084	<5	<1	<1	e
9914	G	082983	<4	3	<1	3
	G	040384	<4	<3	<1	e
9940	G	041084	<4	<3	<1	e
9941	G	082983	<4	2	2	16
		040684	<4	<3	2	8
9942	G	041084	<4	<3	1	1
9943	G	041084	<4	5	<1	6

Table 8.--Concentrations of volatile organic compounds in ground-water samples collected by U.S. Geological Survey 1983-84 (cont.)

A. WELLS (continued)

Well number	Aquifer[1]	Sampling Date (mo,day,yr)[2]	1,2-Dichloro-ethylene	Trichloro-ethylene	Tetrachloro-ethylene	Total VOCs[3]
9950	G	050284	<4	<3	3	7
9951.1	G	080283	<4	4	1	1000
		080283N	<1	<1	<1	e
		101883	<4	4	2	
		101883N	<3	7	4	1200
9951.2	G	043084	<4	<3	<1	5
		043084N	<3	<3	<3	e
9952.1	G	080483	<4	8	<1	9
		102083	<4	6	<1	
		102083N	<3	10	<3	10
9952.2	G	042384	<4	<3	<1	e
		042384N	<3	4	<3	4
9953	G	080483	84	480	3	570
		043084	<4	56	3	64
		043084N	5	200	<3	210
9954	G	080283	61	480	50	600
		080283N	<1	9	3	240
		120183N	10	84	34	130
		041784	<4	92	31	130
		041784N	4	69	28	100
		071984N	39	310	56	410
9955	G	080483	5	5	2	12
		042484	24	440	77	560
9956	G	080583	<4	5	<1	6
		041684	<4	8	<1	8
9957	G	080583	<4	1	<1	2
		042484	<4	<3	<1	e
9958	G	080583	<4	1	<1	1
		041284	<4	<3	<1	e
9959	G	081183	<4	<1	<4	e
		040684	<4	<3	<1	e
9960	G	081183	<4	10	<4	10
		040984	<4	5	1	28
9961	G	081183	<4	<1	<4	e
		040984	<4	<3	1	2

1 G = upper glacial aquifer; M = Magothy aquifer
2 Analyses from same well on same date are of duplicate samples
N = analysis by National Water Quality Laboratory Atlanta, Ga.
3 e=all volatile organic compounds below detection limits

Table 8.--Concentrations of volatile organic compounds in ground-water samples collected by U.S. Geological Survey 1983-84 (cont.)

A. WELLS (continued)

Well number	Aquifer[1]	Sampling Date (mo,day,yr)[2]	1,2-Dichloro-ethylene	Trichloro-ethylene	Tetrachloro-ethylene	Total VOCs[3]
9962	G	081583	<4	<1	<1	10
		040984	<4	<3	<	1
9963	G	081583	<4	6	2	8
		041684	<4	<3	2	6
9964	G	080883	62	290	50	410
		080883N	83	360	67	520
		041984	<4	20	7	27
		041984N	<3	16	8	24
9965.1	G	080483	120	670	4	800
		101883	83	370	2	
		101883N	170	530	5	710
9965.2	G	042384	70	320	1	390
		042384N	<3	270	<3	270
9966	G	080883	40	320	55	430
		041684	<4	3	1	4
		080784	28	350	97	510
9967	G	081183	<4	1	2	3
		040984	<4	<3	<1	e
9968	G	081583	<4	5	3	11
		040684	<4	<3	2	4
9971	G	050884	<5	29	1	32
		080884	130	560	3	700
9972	G	050884	82	440	2	530
		080884	100	360	<4	460
9973	G	050884	140	750	2	890
		080884	130	550	5	690
9974	G	050784	<5	2	<1	2
		080884	<4	1	<4	1
10019	M	081683	<4	19	8	30
		051484	<5	29	12	50
		051484N	7	23	12	42
10020	M	083083	24	170	24	220
		050984	9	150	20	190
10033	M	051584	<5	<1	<1	e
10034	M	101584	<10	<1	<1	4

Table 8.--Concentrations of volatile organic compounds in ground-water samples collected by U.S. Geological Survey 1983-84 (cont.)

A. WELLS (continued)

Well number	Aquifer[1]	Sampling Date (mo,day,yr)[2]	1,2-Dichloro-ethylene	Trichloro-ethylene	Tetrachloro-ethylene	Total VOCs[3]
10035	G	082583	16	72	8	98
		082583N	18	92	13	120
		121383N	36	85	11	130
		022184N	29	79	12	120
		041184	7	70	9	86
		041184N	23	63	11	97
		060484N	11	56	13	80
		080284N	<3	31	10	34
10043	M	080983	<4	2	2	8
		041784	<4	<3	1	9
10076	M	082283	<4	2	<1	7
		042384	<4	<3	<1	e
10094	G	093083	<4	<1	<1	e
		040384	<4	<3	<1	e
10095.1	G	093083	<4	1	5	7
	G	101983	<4	2	4	6
10095.2	G	041684	34	280	2	320
10096.1	G	082583	80	300	44	430
		082583N	140	400	550	1100
		102083	32	220	36	
10096.2	G	050184	<4	19	1	21
		050184N	<3	16	<3	16
		072684N	130	300	74	520
		080784	40	370	110	540
10097.1	G	081783	45	250	39	340
		111583N	38	260	45	340
10097.2	G	050784	<5	2	<1	2
		070284N	16	170	44	230
		080784	17	300	80	450
		091984	25	270	100	460
10202	G	050784	<5	4	<1	4
10204	G	041384	10	210	30	260

1 G = upper glacial aquifer; M = Magothy aquifer
2 Analyses from same well on same date are of duplicate samples
N = analysis by National Water Quality Laboratory, Atlanta, Ga.
3 e = all volatile organic compounds below detection limits

Table 8.--Concentrations of volatile organic compounds in ground-water samples collected by U.S. Geological Survey 1983-84 (cont.)

A. WELLS (continued)

Well number	Aquifer[1]	Sampling Date (mo,day,yr)[2]	1,2-Dichloro-ethylene	Trichloro-ethylene	Tetrachloro-etnylene	Total VOC's[3]
10205	G	041384	12	81	65	160
		050984N	41	72	59	170
		060784N	63	94	100	260
		071284N	15	48	33	96

1 G = upper glacial aquifer; M = Magothy aquifer
2 Analyses from same well on same date are of duplicate samples
3 e All volatile organic compounds below detection limits
*N = Analysis by National Water Quality Laboratory, Atlanta, Ga

B. MISCELLANEOUS SITES

Site[1]	Sampling Date (mo-day-yr)	1,2-Dichloro-ethylene	Trichloro-ethylene	Tetrachloro-ethylene	Total VOCs
PRB in	090783	47	410	61	530
	080784	41	600	150	840
PRB mid	080784	24	380	120	570
NCB 124	090783	24	230	50	310
	080784	17	340	100	490
NCB 167	090783	<4	--	1	1
Aerator (in)[2]	080884	270	1800	15	2100
Aerator (out)[2]	080884	130	1000	3	1100

1 PRB = Pembrook recharge basin. In = inflow to first basin; mid = midpoint = flow to second basin
NCB = Nassau County basin (sampled at inflow) and basin #
2 Aerator = treatment system for wells N9310 and N9311. In = inlet; out = outlet

86-43333

DEPARTMENT OF THE INTERIOR
U.S. GEOLOGICAL SURVEY

PREPARED IN COOPERATION WITH THE
NASSAU COUNTY DEPARTMENT OF PUBLIC WORKS

WATER-RESOURCES INVESTIGATIONS REPORT 86-4333
PLATE 1



WATER-TABLE CONTOURS IN APRIL 1984 AND LOCATION OF WELLS IN THE ROOSEVELT FIELD AREA OF NASSAU COUNTY, LONG ISLAND, NEW YORK

I19.42/4:

86-43333

DEPARTMENT OF THE INTERIOR
U.S. GEOLOGICAL SURVEY

PREPARED IN COOPERATION WITH THE
NASSAU COUNTY DEPARTMENT OF PUBLIC WORKS

WATER-RESOURCES INVESTIGATIONS REPORT 86-4333
PLATE 2





LOCATIONS OF GEOLOGIC SECTIONS









GEOLOGIC SECTIONS A-A', B-B', C-C', D-D', AND E-E' SHOWING 1984 TRICHLOROETHYLENE CONCENTRATIONS IN THE ROOSEVELT FIELD AREA OF NASSAU COUNTY, NEW YORK

I 19 42/4

Best copy available